



**Montara Water  
and Sanitary District**  
*Serving the Community of Montara and Moss Beach*

P.O. Box 370131  
8888 Cabrillo Hwy  
Montara, CA 94037-0131  
t: 650.728.3545 • f: 650.728.8556

---

*To sensitively manage the natural resources entrusted to our care, to provide the people of Montara - Moss Beach with reliable, high – quality water, wastewater, and trash disposal at an equitable price, and to ensure the fiscal and environmental vitality of the district for future generations. Be open to providing other services desired by our community.*

## **REVISED NOTICE OF SPECIAL MEETING**

The Agenda has been revised to allow for  
Director Boyd and Young's participation by teleconference

# **AGENDA**

## **District Board of Directors**

8888 Cabrillo Highway  
Montara, California 94037

**March 27, 2025 at 5:00 p.m.**

The meeting will take place in the District offices located at the above address. Seating is limited and social distancing will be practiced due to ongoing public health and safety concerns. Simultaneous public access and participation is also available remotely, via telephone or the ZOOM application:

### **ZOOM MEETING INFORMATION:**

**WEBSITE:** <https://us02web.zoom.us/j/88606106137?pwd=Xi8Kh7SDftelBU2Z5miahKRU7JdEB5.1>

**MEETING ID:** 886 0610 6137

**Password** 505627

**CALL IN PHONE NUMBER:** +1 669 900 9128

INSTRUCTIONS for remote access are available at <https://support.zoom.us/hc/en-us/articles/201362193-Joining-a-Meeting>. You also may view video during the meeting via live stream or after the meeting at <https://videoplayer.telvue.com/player/wuZKb9gwEY7sMACIIsr7VSJqIB35kNZA/stream/159?fullscreen=true&showtabssearch=false&autostart=false>. If you experience technical difficulties or have technical questions prior to or during the meeting, please contact MWSD's IT support at (650) 728-7843.

Note: Public participation is not permitted during closed session discussion items.

### **Public Comment**

In accordance with the Government Code, members of the public may address the Board on specific agenda items when the matter is announced by the Board President. Any other item of interest that is within the subject matter jurisdiction of the District may be addressed during the Oral Comments portion of the meeting. For participants attending the meeting virtually, a "raise hand" button is available for every Zoom user wishing to speak and should be used to alert the President of the intent to comment.

Upon request, this Agenda and written agenda materials will be made available in appropriate alternative formats to persons with a disability. Request for a disability-related modification or accommodation in order to participate in the public meeting should be emailed to [info@mwsd.net](mailto:info@mwsd.net) or submitted by phone at 650-728-3545 at least two days before the meeting. Requests will be granted whenever possible and resolved in favor of accessibility. Materials related to an item on this Agenda submitted to the Board after distribution of the Agenda Packet are available in the District Clerk's office during normal business hours. Such documents may also be available on the District's web site ([www.mwsd.montara.org](http://www.mwsd.montara.org)) subject to staff's ability to post the documents before the meeting.

## **CALL TO ORDER**

## **ROLL CALL**

## **PRESIDENT'S STATEMENT**

## **ORAL COMMENTS (Items other than those on the agenda)**

## **PUBLIC HEARING**

## **CONSENT AGENDA**

## **OLD BUSINESS**

## **NEW BUSINESS**

1. [Review and Possible Urgency Actions Concerning Seal Cove Critical Geotechnical Hazards Area](#)

## **REPORTS**

## **FUTURE AGENDAS**

## **CONVENE IN CLOSED SESSION**

## **REPORT OF ACTION TAKEN IN CLOSED SESSION, IF ANY**

## **PARTICIPATION BY TELECONFERENCE**

The following Directors will participate by teleconference in all or a portion of the meeting of the Board from the following locations:

Director Boyd -- 139 S. Murphy, Sunnyvale, CA 94086

Director Young – 180 San Lucas Avenue, Moss Beach, CA 94038

## **ADJOURNMENT**

The District has a curfew of 10:30 p.m. for all meetings. The meeting may be extended one hour by vote of the Board.



# MONTARA WATER AND SANITARY DISTRICT AGENDA

For Meeting Of: **March 27, 2025**

TO: BOARD OF DIRECTORS

FROM: Clemens Heldmaier, General Manager

## **SUBJECT: Review and Possible Urgency Actions Concerning Seal Cove Critical Geotechnical Hazards Area**

---

Staff is recommending that the Board take urgency actions for the purpose of emergency repairs, relocation and further investigation to protect District infrastructure in the Seal Cove Critical Geotechnical Hazards Area, an area of documented active landslides, seismic hazards from proximity to earthquake faults and coastal bluff erosion activities, including sea level rise. The area is currently experiencing active land movement, including sinkholes, causing separations and breaks on both District water and sewer mains, as well as private water and sewer laterals. Movement has caused a series of water leaks from District facilities located within portions of public roads, including San Lucas Avenue, west of Del Mar Avenue, Ocean Avenue between San Lucas and Madrone, La Grande Avenue, Los Banos Avenue, as well as the Park Street and Beach Street intersection.

### **History of Land Movement, Including Geotechnical Investigations by San Mateo County**

Seal Cove is located in the southern part of Moss Beach, bounded by Cypress and Bernal Avenues. The Seal Cove area was subdivided into residential parcels about 1908. In the late 1960's, the U.S. Geological Survey slowed Seal Cove development due to active landsliding and accelerated coastal erosion. San Mateo County froze building construction and authorized a detailed geologic study of the area intended to provide guidelines for future development. The geologic study, completed in 1971, confirmed active landsliding, faulting, and seacliff erosion, and outlined requirements for development in some areas of Seal Cove. Some residential single family home development continued.

In 1980, the County Planning Department once again commissioned a geologic report titled "Geologic Analysis of the Seal Cove Area County of San Mateo" which designated the Seal Cove study area into 3 risk zones on the basis of similar geotechnical hazards, as shown on the attached map designated "Geologic Analysis of the Seal Cove Area". (A copy of the full study is attached to the proposed interim urgency ordinance, also submitted with this agenda item.) The purpose of the study was to identify the geologic hazards to inform future land use decisions by the County and the official land use policy to guide future development in the Seal Cove area. The study confirmed continued instability and geologic hazards, including



# MONTARA WATER AND SANITARY DISTRICT AGENDA

For Meeting Of: **March 27, 2025**

TO: BOARD OF DIRECTORS

FROM: Clemens Heldmaier, General Manager

approximately 17 homes that had suffered some form of structural damage due to landslide activity. The report further identified 3 geologic hazard zones, and risk for each zone, including active hazards in Zone 1:

*Zone 1 Risk Assessment – UNSTABLE; Risk to development in this zone is considered to be extremely high. It is reasonable to conclude that slow progressive landsliding and seacliff retreat will continue, resulting in structural and property damage. This is especially true for structures or utilities located astride active surface breaks. Rapid catastrophic slope failure of the high, steep portion of the seacliff located west of Ocean Boulevard is a clear probability. Such an event could involve the loss of life as well as significant property damage. The feasibility of reducing the risk to acceptable levels is extremely low. No additional development should be allowed in this zone.*

The 1980 report further recommended that the entire study area, i.e., all 3 hazard zones, be designated a critical hazards area in order to establish prudent land use policies within the Seal Cove area:

Critical Hazards Area - Due to the complexity of the hazardous geologic conditions in the Seal Cove area we recommend that the entire study area be designated as a “Critical Geotechnical Hazards Area.” Such a designation would the region as an area of high geologic hazards for which special or more detailed geologic and soil investigations (i.e. geotechnical) will be required prior to development. Additionally, such a designation would alert present and future landowners to the hazardous conditions and the potential higher than normal cost of development.<sup>1</sup>

---

<sup>1</sup>Based on the 1980 Seal Cove Area study and map, the County established the GH (Geologic Hazard District) zoning district to regulate development in the area. The purpose of the GH District is to safeguard to safeguard life, limb, property and the public welfare by regulating land development in areas determined to be hazardous for development because of geologic factors. Among other things, building permits issued in the area are subject to the following deed restriction:

This property is located in Zone of the Seal Cove Geologic Hazards District established by Section 6296 of the San Mateo County Ordinance Code, Zoning Annex. Maps of this district are on file with the County Geologist and the Planning Division, Department of Environmental Management, San Mateo County.



# MONTARA WATER AND SANITARY DISTRICT AGENDA

For Meeting Of: **March 27, 2025**

TO: BOARD OF DIRECTORS

FROM: Clemens Heldmaier, General Manager

Since 1979, four houses west of Ocean Boulevard have been relocated or demolished. San Mateo County closed Ocean Boulevard between Los Banos and San Lucas Avenues first in 1995, allowed it to be reopened, and then closed it permanently in 2006. Additionally, Ocean Blvd between the Moss Beach Distillery and San Lucas Avenue was permanently closed by 2011 due to ongoing land movement.

Land in this area has continued to slump and heave over time, resulting in a lowering of elevation for many properties. There has been very active land movement in over the last two years, and the extremely active emergency developing over the last two-three weeks (discussed below). Many sewers in the Seal Cove area originally flowed by gravity towards Highway 1. In the 1980's however, the addition of sump and sewage pumps was necessary to bring private property sewage uphill to the District's system. These sump and sewage pumps were funded, constructed and to be maintained by the formation of an assessment district in the Seal Cove area.

## **Recent Leaks Indicate New Land Movement; Repairs and Immediate Actions to Maintain Service to Three Critically Affected Properties**

Since mid-February, the District has responded to 10 water leaks and repaired 8 leaks on either a District water main or individual property water connections near San Lucas Avenue and Ocean Boulevard. This is a clear indication of additional land movement. MWSD staff – who are on call 24 hours a day to repair leaks – took quick action to fix these leaks, and also relocated a water connection for 1 home, and provided above ground water connections for 2 homes on San Lucas. Further, in recent days staff has become aware of a PG&E gas leak, an electric pole connection pulled out of a single-family home, at least four sewer issues (separations or pump failures) on private sewer assets, as well as an ambulance that was stranded on San Lucas due to land movement, open fissures and settling in the street surface.

Staff additionally tested and visually inspected District sewers to confirm no breaks that would allow untreated sewage into the soils or coastal environment.

---

The Seal Cove Area is further subject to San Mateo County's certified Local Coastal Plan polices designed to minimize risks to life and property, defines and designates hazardous areas, and regulates development on blufftops including requirements for blufftop setback distances.



# MONTARA WATER AND SANITARY DISTRICT AGENDA

For Meeting Of: **March 27, 2025**

TO: BOARD OF DIRECTORS

FROM: Clemens Heldmaier, General Manager

The water main in San Lucas has been capped at the western side of the Del Mar intersection. District staff have rerouted the water main mid-block on San Lucas west of Del Mar to maintain water supply to the fire hydrant at this intersection, and to connect into the water main on Del Mar. Staff are working to further protect District water and sewer infrastructure in this area to reduce the potential for any future water or sewage leaks.

To restore service to two homes on San Lucas (86 and 89 San Lucas Avenue), District staff have assisted in providing above ground water service connections between the affected properties and either an adjacent neighboring property willing to allow the hose bib connection or via the District's water mains. These above ground connections provide a safer water service connection by providing the property owners visual access to their water service line, eliminates the need for District or contractor staff to excavate in unstable soils, and reduces the risk to District infrastructure.

San Mateo County previously closed San Lucas Avenue from Del Mar Avenue to Ocean Boulevard, and will not allow excavation permits for any District work in this closed area. The District General Manager has been in contact with County staff as well as Supervisor Mueller's office regarding the current emergency situation. The County has indicated concerns about issuing additional building permits in the future and will work with MWSD to ensure that the issues are appropriately addressed.

## **Further Action Needed to Protect District Infrastructure, Public Health and the Environment**

This recent land movement in an active geologic hazard area indicates increased risk for District assets, as well as District staff working in the area. Safe work conditions for subsurface infrastructure repairs are not possible in an area of active landslide movement. The high likelihood of increased leaks and damage to District water and sewer pipelines is unsustainable, and contrary to our mission to protect public health and the environment.

The District is working to rapidly review existing geotechnical reports to determine the safest location for District assets. The District is examining the need to cap or relocate additional water mains and sewer mains outside of the geologic hazard zones. This may require customers to relocate their water connections and for some properties to maintain above ground water connections. Because of this critical and





# MONTARA WATER AND SANITARY DISTRICT AGENDA

For Meeting Of: **March 27, 2025**

TO: BOARD OF DIRECTORS

FROM: Clemens Heldmaier, General Manager

developing situation directly affecting the District's ability to provide essential services, staff is recommending that the District temporarily suspend accepting and issuing sewer or water permits, including but not limited to, reactivating inactive services, permitting or allowing any service activities in the Seal Cove Area that are deemed by the District's General Manager or the District's Engineer's necessary to protect public health and safety, the environment and the District's system facilities from pipeline failures/service interruptions, sinkholes or further land destabilization and potential environmental contamination from leaks in this high-risk area. Compliance with the District's legal and regulatory obligations to provide safe and reliable service and prevent infrastructure failures that are likely to cause severe environmental harm is of the highest concern.

## **Coordination with San Mateo County, and Coastside County Fire Protection District, as well as Updating Affected Property Owners; Researching Potential Funding for District Infrastructure Work, as well as Property Owner Support through San Mateo County**

District staff have been actively working with San Mateo County and Coastside Fire Protection District to alert them to these new leaks and land movement. We will continue to coordinate as we determine the best path forward for District infrastructure and safe working conditions.

Staff have provided a written update to the two critically affected homeowners and plans to provide a further update to the residents of the broader Seal Cove area, once additional water and sewer work is defined and scheduled.

Staff are working to identify any grant opportunities that could fund this emergency work and continue to work with San Mateo County to seek funding opportunities the County can access to support impacted residents.

Based on the above, staff is recommending that the Board make certain findings and take interim and urgency actions necessary to prevent or mitigate loss of, or damage to, life, health, property and essential public services. In particular, staff recommends the following actions:

- Authorize the General Manager to take emergency actions and expend necessary funds to respond to infrastructure threats in the Seal Cove Area;





# MONTARA WATER AND SANITARY DISTRICT AGENDA

For Meeting Of: **March 27, 2025**

TO: BOARD OF DIRECTORS

FROM: Clemens Heldmaier, General Manager

- Direct and authorize staff to review or conduct geotechnical studies and evaluate the District's facilities to inform potential infrastructure vulnerabilities, assess short and long-term stability of proposed improvements and make recommendations regarding same;
- Temporarily suspend issuing new service permits and related restrictions in the Seal Cove Area for a period of 60 days;
- Authorize the General Manager to request state and federal financial assistance under the San Mateo County Multijurisdictional Local Hazard Mitigation Plan (LHMP) through the MWSD LHMP Annex;<sup>2</sup>
- Approve and authorize submittal of a letter to the County of San Mateo (attached) on behalf of MWSD requesting its collaboration and assistance in applying the County's land use policies for temporary and/or permanent regulation of development in the Seal Cove area; and further requesting that the County proclaim a local emergency by virtue of its authority under the California Emergency Services Act and the California Disaster Assistance Act. This requested action is in addition to, and intended to supplement financial assistance that may be available through the District's participation in the LHMP.

The requirements for the above recommended actions are set forth in the attached proposed emergency resolutions and interim ordinance.

## RECOMMENDATION:

### **Adopt:**

1. RESOLUTION OF THE MONTARA WATER AND SANITARY DISTRICT DECLARING EXISTENCE OF EMERGENCY CONDITION REQUIRING IMMEDIATE EXPENDITURE OF

---

<sup>2</sup> In 2023, this Board adopted a Universal Resolution that covers all declared disasters for up to three (3) years without approval of separate resolutions for each individual disaster during this timeframe. This Resolution is required for any Request for Public Assistance (RPA) by the District and it designated MWSD's General Manager as the Designated Authorized Agent on behalf of the District. Having passed the Resolution allows the District to apply for federal financial assistance for any existing or future grant program.



# MONTARA WATER AND SANITARY DISTRICT AGENDA

For Meeting Of: **March 27, 2025**

TO: BOARD OF DIRECTORS


FROM: Clemens Heldmaier, General Manager

FUNDS AND OTHER ACTIONS IN FURTHERANCE OF PUBLIC HEALTH, WELFARE AND SAFETY, AND APPROVING AND RATIFYING EXECUTION OF CONTRACTS FOR REPAIR OF ESSENTIAL PUBLIC FACILITIES RELATING THERETO (Seal Cove Critical Geotechnical Hazards Area)

2. RESOLUTION OF THE BOARD OF DIRECTORS OF THE MONTARA WATER AND SANITARY DISTRICT DECLARING THE EXISTENCE OF AN EMERGENCY WITHIN A PORTION OF THE DISTRICT'S SERVICE AREA DUE TO ACTIVE LAND INSTABILITY, COASTAL BLUFF SOIL EROSION, SEISMIC HAZARDS AND THREAT OF ESSENTIAL PUBLIC INFRASTRUCTURE DAMAGE AND URGING THE COUNTY OF SAN MATEO TO PROCLAIM A LOCAL EMERGENCY (SEAL COVE CRITICAL GEOLTECNICAL HAZARDS AREA)
  
3. INTERIM URGENCY ORDINANCE OF THE BOARD OF DIRECTORS OF THE MONTARA WATER AND SANITARY DISTRICT TEMPORARILY SUSPENDING THE ISSUANCE OF WATER AND SEWER SERVICE PERMITS OR OTHERWISE RESTRICTING SAID SERVICE WITHIN THE SEAL COVE CRITICAL GEOLTECNICAL HAZARDS AREA

## Attachments

- William Cotton and Associates, Geotechnical Consultants, "Geologic Analysis of the Seal Cove Area County of San Mateo", including Seal Cove Geotechnical Hazards Map (1980)
- Proposed Letter to San Mateo County Board of Supervisors
- Proposed Resolutions and Interim Ordinance



ATTACHMENT TO STAFF  
REPORT, PAGE 1 OF 2

SEAL COVE  
GEOLOGICAL HAZARDS ZONES


**William Cotton and Associates** GEOTECHNICAL CONSULTANTS  
341 10TH AVE., LOS GATOS, CA 95030

**GEOTECHNICAL HAZARDS MAP**  
**SEAL COVE STUDY AREA**

PLATE NO. 1 SCALE: 1"=200' DATE: 8/5/80  
PROJECT NO. G 112-80 GEO./ENG. BY: WCA APPROVED BY: WCA

# Geologic Analysis of the Seal Cove Area


## GEOTECHNICAL HAZARDS MAP



## EXPLANATION

GEOTECHNICAL HAZARD ZONE	RISK ASSESSMENT	REQUIRED GEOTECHNICAL INVESTIGATION
<p><b>ZONE 1</b></p> <ul style="list-style-type: none"> <li>Includes all lands located along the western scarp that are adversely affected by active landslide processes and accelerated scarp erosion. The position of the eastern boundary of this zone is established by the easternmost extent of active landsliding plus a setback of 50 feet. The setback zone includes lands which lie outside or east of the active landslides but are expected to experience problems in the future (i.e. 50 years).</li> </ul>	<p><b>UNSTABLE</b></p> <ul style="list-style-type: none"> <li>Risk to development in this zone is considered to be extremely high. It is reasonable to conclude that slow progressive landsliding and scarp retreat will continue, resulting in structural and property damage. This is especially true for structures or utilities located astride active surface breaks. Rapid catastrophic slope failure of the high, steep portion of the scarp located west of Ocean Boulevard is a clear probability. Such an event could involve the loss of life as well as significant property damage. The feasibility of reducing the risk to acceptable levels is extremely low.</li> <li>No additional development should be allowed in this zone.</li> </ul>	<ul style="list-style-type: none"> <li>No investigation deemed feasible due to the severity of the instability.</li> </ul>
<p><b>ZONE 2</b></p> <ul style="list-style-type: none"> <li>Includes all lands within a 100-foot wide zone located immediately adjacent to the zone of active landsliding and accelerated scarp erosion (i.e. Zone 1). The position of the eastern boundary of this zone is established in part by an approximate 2:1 (i.e. 76.2 degrees) projection measured from the base of the high scarp located west of Ocean Boulevard.</li> </ul>	<p><b>QUESTIONABLE STABILITY</b></p> <ul style="list-style-type: none"> <li>Risk to development in this zone is considered to be moderate to high. Forward progression of active landsliding is difficult to predict with reliable accuracy. The likelihood of eliminating the risk is very low, however it may be possible to significantly reduce foundations.</li> <li>No development should be allowed in this zone until stability is clearly demonstrated by the required geotechnical investigations.</li> </ul>	<ul style="list-style-type: none"> <li>Engineering geologic investigation by a certified engineering geologist and a soil and foundation engineering investigation by a registered civil engineer, or a combined equivalent of the above.</li> <li>Scope of both investigations should be directed toward a detailed evaluation of the potential landslide hazards in this zone. In most cases, landslide studies will require extensive subsurface work in order to provide the necessary technical data to conduct a detailed slope stability analysis. The geotechnical analysis should provide acceptable factors of safety to clearly demonstrate stability before construction is allowed in this zone.</li> </ul>
<p><b>ZONE 3</b></p> <ul style="list-style-type: none"> <li>Includes all lands located outside of the areas affected by active or potential landslides.</li> </ul>	<p><b>MOST STABLE</b></p> <ul style="list-style-type: none"> <li>Risk to development in this zone is considered to be low to moderate. The major geologic hazard in this zone is the threat of surface faulting along the master fault trace and several branching fault traces of the Seal Cove fault. These faults are active and capable of producing damaging surface faulting, strong ground shaking and ground failure.</li> <li>The relative risk associated with poor surface drainage and potentially expansive soils is generally regarded as moderate to locally high.</li> <li>The feasibility of reducing the risks to acceptable levels in this zone is considered high. This can be accomplished by careful siting of homes away from active faults, using careful structural and foundation design and adequate surface drainage plans. However, it is possible that some residential parcels will be judged unbuildable due to high seismic hazards.</li> <li>Development should be allowed in this zone on parcels found to be free of hazardous conditions by the required geotechnical investigations.</li> </ul>	<ul style="list-style-type: none"> <li>Engineering geologic investigation by a certified engineering geologist and a soil and foundation engineering investigation by a registered civil engineer, or a combined equivalent of the above, unless evidence is available to show that such investigations are not required.</li> <li>Scope of engineering geologic investigation should address the seismic hazards related to the master and branching traces of the Seal Cove fault. Particular emphasis of the engineering geologic investigations should be placed on the evaluation of possible surface faulting. Investigative techniques within this area will require the use of subsurface trenching and possibly geophysical traverses unless clear evidence is established to show that no active fault crosses the parcel in question.</li> <li>The soil and foundation engineering investigation should address, but not necessarily be confined to the following items: site preparation and grading, surface drainage, and design parameters for residential foundations.</li> </ul>

### MAP SYMBOLS



### NOTES TO USERS

This map provides geotechnical data based on detailed surface mapping, interpretation of aerial photographs and the geologic data presented in the report entitled **Geologic Report of Seal Cove - West Beach Area**, October 14, 1977, by **W. Leighton and Associates**. The map is primarily designed for use by geologists, engineers and planners and is not intended to be a substitute for detailed site specific geotechnical investigations.

Additional description and explanation of the geologic conditions of the Seal Cove Study Area may be found in the accompanying report entitled **Geologic Analysis of the Seal Cove Area, County of San Mateo, August 3, 1980** by **William Cotton and Associates**.

RESOLUTION NO. \_\_\_\_\_

**A RESOLUTION OF THE BOARD OF DIRECTORS OF THE MONTARA WATER AND SANITARY DISTRICT DECLARING THE EXISTENCE OF AN EMERGENCY WITHIN A PORTION OF THE DISTRICT'S SERVICE AREA DUE TO ACTIVE LAND INSTABILITY, COASTAL BLUFF SOIL EROSION, SEISMIC HAZARDS AND THREAT OF ESSENTIAL PUBLIC INFRASTRUCTURE DAMAGE AND URGING THE COUNTY OF SAN MATEO TO PROCLAIM A LOCAL EMERGENCY (SEAL COVE CRITICAL GEOLTECNICAL HAZARDS AREA)**

**WHEREAS**, the Montara Water and Sanitary District ("District or MWSD") is a Sanitary District duly organized under the Sanitary District Act of 1923 (Health & Safety Code §§ 6400 – 6830) and a public agency formed as a special district and authorized under California law, by a special election of August 11, 1992 and MWSD Resolution 978 to exercise all powers of a county water district in the same manner as county water districts formed under the County Water District Law (Division 12 (commencing with Section 30000) of the Water Code) and responsible for the provision of essential water and sewer services to the communities of Montara and Moss Beach; the District is authorized to exercise its powers to take appropriate measures and actions to prevent or mitigate an emergency necessary to protect the public safety, health and environment and respond to infrastructure threats; and

**WHEREAS**, on or about March 16 2025, the District was alerted to active land movement along the coastal bluff in the Seal Cove Critical Geotechnical Hazards Area ("Area or Seal Cove Area"), including sinkholes, causing a series of line breaks and water leaks of MWSD infrastructure located within portions of public roads, including San Lucas Avenue, west of Del Mar Avenue, Ocean Avenue between San Lucas and Madrone, La Grande Avenue, Los Banos Avenue, as well as the Park Street and Beach Street intersection; Additionally, since mid-February, staff has responded to ten (10) water leaks and repaired eight (8) leaks on either a District water main or individual property water connections near San Lucas Avenue and Ocean Boulevard; and

**WHEREAS** the Area lies along the Seal Cove earthquake fault line and numerous branch lines which are considered to be active and has long been designated by the County of San Mateo as a Geotechnical Hazard Area with low coastal cliff stability. The Area has been extensively studied regarding geotechnical and natural hazards that subject it to active landslides, seismic hazards, sea cliff erosion and sea level rise. A 1980 study identified four (4) Geotech zones (attached as Exhibit A is the Geologic Hazard Zone Study and Map) currently used by San Mateo County, the local agency with land use authority, as the guide for development in the Seal Cove Area; and

**WHEREAS** the ongoing land movement and cliffside instability in the Area and portions of MWSD's service area threatens the integrity of sewer and water supply lines and mains, increasing the risk of line breaks, sewage overflows,

RESOLUTION NO. \_\_\_\_\_

**A RESOLUTION OF THE BOARD OF DIRECTORS OF THE MONTARA WATER AND SANITARY DISTRICT DECLARING THE EXISTENCE OF AN EMERGENCY WITHIN A PORTION OF THE DISTRICT'S SERVICE AREA DUE TO ACTIVE LAND INSTABILITY, COASTAL BLUFF SOIL EROSION, SEISMIC HAZARDS AND THREAT OF ESSENTIAL PUBLIC INFRASTRUCTURE DAMAGE AND URGING THE COUNTY OF SAN MATEO TO PROCLAIM A LOCAL EMERGENCY (SEAL COVE CRITICAL GEOLTECNICAL HAZARDS AREA)**

water loss, service interruptions and potential contamination of the District's water supply, including groundwater and coastal waters, making it unsafe to extend water and sewer service to properties in the Areas; and

**WHEREAS** MWSD's infrastructure in unstable areas is not designed to withstand ongoing ground movement, and new connections could exacerbate system failures and costly emergency repairs. Further, increased development in unstable areas would place excessive strain on MWSD's system, jeopardizing service reliability for existing customers. MWSD must prioritize infrastructure stabilization and maintenance over continued use or expansion in high-risk areas; and

**WHEREAS**, certain critical infrastructure, including water pipelines and sewer lines, is located within public roadways along the coastal bluff which is vulnerable to soil erosion, land instability, sea level rise, and the potential effects of earthquake fault lines which pose a severe and imminent threat to the safety of the District's infrastructure and, by extension, to public health and safety; and

**WHEREAS** the conditions currently existing present a grave threat to the continued operation of the water and sewer system, as well as the public roadways, with the potential for catastrophic infrastructure failure, disruption of service, or environmental harm to the surrounding area; and

**WHEREAS** immediate corrective actions are necessary to mitigate risks to critical infrastructure and protect the community, including the initiation of emergency repairs, stabilization measures and related conditions associated with development in the Area to ensure service continuity; and

**WHEREAS**, the above recited conditions warrant and necessitate that the District declare the existence of an emergency within its jurisdiction and the powers, functions, and duties of the District shall be those prescribed by state law and by ordinances and resolutions of the District Board to ensure the continuation of critical services, to protect the safety of customers and to provide for immunities that will protect the District for such actions taken; and,

RESOLUTION NO. \_\_\_\_\_

**A RESOLUTION OF THE BOARD OF DIRECTORS OF THE MONTARA WATER AND SANITARY DISTRICT DECLARING THE EXISTENCE OF AN EMERGENCY WITHIN A PORTION OF THE DISTRICT'S SERVICE AREA DUE TO ACTIVE LAND INSTABILITY, COASTAL BLUFF SOIL EROSION, SEISMIC HAZARDS AND THREAT OF ESSENTIAL PUBLIC INFRASTRUCTURE DAMAGE AND URGING THE COUNTY OF SAN MATEO TO PROCLAIM A LOCAL EMERGENCY (SEAL COVE CRITICAL GEOLTECNICAL HAZARDS AREA)**

**WHEREAS**, the governing body of the County of San Mateo is the local body with land use regulatory authority over development in the Area, including maintenance of County road system, and has the power to proclaim a local emergency under the provisions of the California Emergency Services Act (Government Code Sections 8630 et seq.) and the California Disaster Assistance Act (Government Code Sections 8680 et seq.) due to the immediate and impending risks posed by soil erosion, land instability, and other related natural threats to public roads and the District's infrastructure; and

**WHEREAS** the governing body of the County of San Mateo has the further authority to take urgency measures, including interim ordinances, prohibiting or restricting land uses within the Area to protect the public safety, health and welfare; and

**WHEREAS** the conditions described herein warrant and necessitate that the County of San Mateo proclaim a local emergency within its jurisdiction to provide for the protection of life, property, and the environment and to assist the District in its efforts.

**NOW, THEREFORE, BE IT RESOLVED** that the Board of Directors of the District hereby declares the existence of an emergency within its service area jurisdiction and directs District staff to take the necessary steps and appropriate actions to mitigate the threat to District infrastructure, including but not limited to the procurement of emergency contracts, the initiation of emergency stabilization efforts and other protections to the District's facilities, and request for mutual aid or state and federal assistance under applicable laws; and

IT IS FURTHER RESOLVED that during the existence of said District emergency, the General Manager, including through District staff, address the risks posed to the District's critical functions and response efforts, including in coordination with the appropriate departments of the County of San Mateo; and

IT IS FURTHER RESOLVED that the General Manager provide written notice of this emergency declaration to the governing body of the County of San Mateo, along with the District's request collaboration and assistance, including the that the County proclaim a local emergency as required by law.



RESOLUTION NO. \_\_\_\_\_

**A RESOLUTION OF THE BOARD OF DIRECTORS OF THE MONTARA WATER AND SANITARY DISTRICT DECLARING THE EXISTENCE OF AN EMERGENCY WITHIN A PORTION OF THE DISTRICT'S SERVICE AREA DUE TO ACTIVE LAND INSTABILITY, COASTAL BLUFF SOIL EROSION, SEISMIC HAZARDS AND THREAT OF ESSENTIAL PUBLIC INFRASTRUCTURE DAMAGE AND URGING THE COUNTY OF SAN MATEO TO PROCLAIM A LOCAL EMERGENCY (SEAL COVE CRITICAL GEOLTECNICAL HAZARDS AREA)**

BE IT FURTHER RESOLVED that the Board will review this declaration of emergency every sixty (60) days to assess the ongoing conditions and any necessary adjustments to the response efforts; and

IT IS FURTHER RESOLVED that this Resolution shall be effective upon adoption and that publicity and notice shall be given through the most feasible and adequate means of dissemination.

\_\_\_\_\_  
President, Montara Water and Sanitary District

COUNTERSIGNED:

\_\_\_\_\_  
Secretary, Montara Water and Sanitary District

\* \* \* \*

I HEREBY CERTIFY that the foregoing Resolution No. \_\_\_\_\_ duly and regularly adopted and passed by the Board of the Montara Water and Sanitary District, County of San Mateo, California, at a Special Adjourned Meeting thereof held on the 27th day of March 2025, by the following vote:

AYES, Directors:

ABSTENTION:

NOES, Directors:

ABSENT, Directors:

\_\_\_\_\_  
Secretary, Montara Water and Sanitary District




# Geologic Analysis of the Seal Cove Area

## EXHIBIT A

### GEOTECHNICAL HAZARDS MAP SEAL COVE STUDY AREA

PLATE NO. 1    SCALE: 1"=200'    DATE: 8/5/80  
 PROJECT NO. G 112-80    GEO./ENG. BY: [Signature]    APPROVED BY: WRC


#### GEOTECHNICAL HAZARDS MAP



#### EXPLANATION

GEOTECHNICAL HAZARD ZONE	RISK ASSESSMENT	REQUIRED GEOTECHNICAL INVESTIGATION
<b>ZONE 1</b> ■ Includes all lands located along the western seaciff that are adversely affected by active landslide processes and accelerated seaciff erosion. The position of the eastern boundary of this zone is established by the easternmost extent of active landsliding plus a setback of 50 feet. The setback zone includes lands which lie outside or east of the active landslides but are expected to experience problems in the future (i.e. 502 years).	<b>UNSTABLE</b> ■ Risk to development in this zone is considered to be extremely high. It is reasonable to conclude that slow progressive landsliding and seaciff retreat will continue, resulting in structural and property damage. This is especially true for structures or utilities located astride active surface breaks. Rapid catastrophic slope failure of the high, steep portion of the seaciff located west of Ocean Boulevard is a clear probability. Such an event could involve the loss of life as well as significant property damage. The feasibility of reducing the risk to acceptable levels is extremely low. ★ No additional development should be allowed in this zone.	■ No investigation deemed feasible due to the severity of the instability.
<b>ZONE 2</b> ■ Includes all lands within a 100-foot wide zone located immediately adjacent to the zone of active landsliding and accelerated seaciff erosion (i.e. Zone 1). The position of the eastern boundary of this zone is established in part by an approximate 2:1 (i.e. 261 degrees) projection measured from the base of the high seaciff located west of Ocean Boulevard.	<b>QUESTIONABLE STABILITY</b> ■ Risk to development in this zone is considered to be moderate to high. Eastward progression of active landsliding is difficult to predict with reliable accuracy. The likelihood of eliminating the risk is very low, however it may be possible to significantly reduce the impact of the hazard by properly designed foundations. ★ No development should be allowed in this zone until stability is clearly demonstrated by the required geotechnical investigations.	■ Engineering geologic investigation by a certified engineering geologist and a soil and foundation engineering investigation by a registered civil engineer, or a combined equivalent of the above. • Scope of both investigations should be directed toward a detailed evaluation of the potential landslide hazards in this zone. In most cases, landslide studies will require extensive subsurface work in order to provide the necessary technical data to conduct a detailed slope stability analysis. The geotechnical analysis should provide acceptable factors of safety to clearly demonstrate stability before construction is allowed in this zone.
<b>ZONE 3</b> ■ Includes all lands located outside of the areas affected by active or potential landslides.	<b>MOST STABLE</b> ■ Risk to development in this zone is considered to be low to moderate. The major geologic hazard in this zone is the threat of surface faulting along the master fault trace and several branching fault traces of the Seal Cove fault. These faults are active and capable of producing damaging surface faulting, strong ground shaking and ground failure. The relative risk associated with poor surface drainage and potentially expansive soils is generally regarded as moderate to locally high. The feasibility of reducing the risks to acceptable levels in this zone is considered high. This can be accomplished by careful siting of homes away from active faults, using careful structural and foundation design and adequate surface drainage plans. However, it is possible that some residential parcels will be judged unbuildable due to high seismic hazards. ★ Development should be allowed in this zone on parcels found to be free of hazardous conditions by the required geotechnical investigations.	■ Engineering geologic investigation by a certified engineering geologist and a soil and foundation engineering investigation by a registered civil engineer, or a combined equivalent of the above, unless evidence is available to show that such investigations are not required. • Scope of engineering geologic investigation should address the seismic hazards related to the master and branching traces of the Seal Cove fault. Particular emphasis of the engineering geologic investigations should be placed on the evaluation of possible surface faulting. Investigative techniques within this area will require the use of subsurface trenching and possibly geophysical traverses unless clear evidence is established to show that no active fault crosses the parcel in question. • The soil and foundation engineering investigation should address, but not necessarily be confined to, the following items: site preparation and grading, surface drainage, and design parameters for residential foundations.

#### MAP SYMBOLS



#### NOTES TO USERS

■ This map provides geotechnical data based on detailed surface mapping, interpretation of aerial photographs and the geologic data presented in the report entitled *Geologic Report of Seal Cove - Moss Beach Area*, October 15, 1971 by F. Beach Leighton and Associates. The map is primarily designed for use by geologists, engineers and planners and is not intended to be a substitute for detailed site specific geotechnical investigations.  
 Additional description and explanation of the geologic conditions of the Seal Cove study area may be found in the accompanying report entitled *Geologic Analysis of the Seal Cove Area, County of San Mateo*, August 5, 1980 by William Cotton and Associates.



GEOLOGIC ANALYSIS  
OF THE  
SEAL COVE AREA  
COUNTY OF SAN MATEO

100-100-100  
100-100-100  
100-100-100





William Cotton  
and Associates

GEOTECHNICAL CONSULTANTS

314 Tait Avenue, Lbs Gatos, California 95030  
(408) 354-5542

David C. Hale, Director  
Planning Department  
County of San Mateo  
590 Hamilton Street  
Redwood City, California 94063

August 5, 1980  
G112-80

Dear Mr. Hale:

In accordance with our agreement with the County of San Mateo (#5500-80-426) dated July 14, 1980, the final geologic report is hereby submitted.

As a result of our work, the original Geologic Map of the Seal Cove area has been updated and a number of recommendations are presented herein in order to help strengthen the present land use policies that control development.

Our report is presented in two basic parts consisting of a Conclusions and Recommendations section followed by a Technical Report section. The technical report describes the geologic data and analysis that we used to support the final conclusions and recommendations.

It has been our pleasure to be of service to the County on this interesting project. If we can be of help in clarifying any aspect of this report, please do not hesitate to contact our office.

Sincerely yours,

WILLIAM COTTON AND ASSOCIATES

William R. Cotton  
Engineering Geologist, CEG 882

bp

Attached report



CONCLUSIONS  
AND  
RECOMMENDATIONS

GEOLOGIC  
ANALYSIS  
OF THE  
SEAL COVE AREA

COUNTY OF SAN MATEO  
CALIFORNIA

August 1980





## CONCLUSIONS

The Seal Cove study area is exposed to a variety of geologic hazards that severely affect future land use decisions. These conditions and the level of associated risk were well documented nearly a decade ago by a County-authorized geologic study conducted by Leighton and Associates (October 1971). The present study was designed to update the geologic information presented in the Leighton report and to reevaluate the residential development regulations.

The following geologic hazards are the principal geologic concerns of the Seal Cove area:

Landsliding - Deep-seated landslides presently are destroying extensive sections of the seacliff region which define the western edge of the study area. Approximately 17 homes have suffered some form of structural damage due to landslide activity. The inland extent of the active landsliding from the coastline ranges between 100 to 400 feet; however, the average distance is nearly 250 feet. The average rate of landslide movement is very slow, probably ranging between 1 and 3 inches per year. However, the probability of accelerated movements is considered high in many local areas within the presently failing landslide complex. This is especially true of the high seacliff area located west of Ocean Boulevard where rapid catastrophic failure is a clear possibility.

Faulting - The active Seal Cove fault and a number of branching fault traces pass through the study area. The main trace is confined to a 100-foot-wide zone located along the eastern margin of the study area. Although most of this zone lies outside of the study area, the branching fault traces pass through the main portion of the residential area. All of these faults are considered to be active, and thus, capable of generating earthquakes with associated ground shaking, surface faulting and ground failure.

Seacliff Erosion - The entire coastline area presently is experiencing severe erosion by wave activity. This erosion process causes the seacliff to become undercut at its base and locally unstable. The oversteepened face of the seacliff responds by shallow, piecemeal sloughing; however, natural stability is never achieved due to the constant erosional activity within the surf zone. The result is a systematic retreat of the seacliff by local episodic sloughing. The average rate of cliff retreat is approximately 3 to 4 feet per year in the Seal Cove area.

A number of additional geologic problems have been identified in the Seal Cove area; however, these are

relatively minor hazards when compared to those outlined above and can be significantly mitigated by design. These problems include potentially expansive soils, poor surface drainage and problems associated with shallow ground water.

### RISK ANALYSIS

The development of sound public policy to deal with the geologic hazards of the Seal Cove area requires an answer to the question, "How safe is safe enough?" The information and analysis presented in this report is an attempt to provide the necessary framework on which the appropriate County decisionmakers can judge acceptable levels of risk.

To properly assess the appropriate level of risk to the community, a number of important steps are essential. First, and probably most importantly, the presence of geologic hazards must be recognized. In the Seal Cove area, although the original subdivision was initiated in the early 1900's, the hazardous landslide and fault conditions were not recognized until nearly ten years ago. Consequently, many homes and streets were built on active landslides or astride active traces of the Seal Cove fault, and thus, have sustained considerable damage.

The second step in this process takes place after the geologic hazards have been recognized. This step requires detailed studies to determine the physical characteristics of the hazards. For the Seal Cove area, this was accomplished through the initial geologic study conducted by Leighton and Associates in 1971. They identified a large area of active landslides, and a number of fault traces associated with the Seal Cove fault. As an important part of their investigation, they provided a detailed description of the dimensions and level of activity of the landslides and faults.

Once the geologic hazards are recognized and carefully characterized, then the degree or level of risk associated with each hazard can be evaluated. In the Seal Cove area the present land use tends to limit the exposure of risk mainly to utilities, streets and houses; however, the potential for personal injury or loss of life is possible in local areas. The decision as to whether the various levels of risk are tolerable or intolerable to the public requires the input of the County decisionmakers. An important part of any risk analysis is the consideration of possible mitigating measures that could reduce the risk associated with each type of hazard. This kind of action is usually the product of the democratic process and depends as much on social, economic and environmental values as on geologic knowledge. There are a number of mitigating measures that may reduce risk to tolerable levels. For example, land use may be regulated to the degree that residential development is simply restricted from

hazardous areas, thus the hazard is avoided and the risk is essentially eliminated. This has been done in the Seal Cove area by prohibiting construction in active landslide areas, astride active fault traces and close to the edge of the seacliff.

Another method of reducing the risk is by attempting to reduce the impact of the hazard. This might include requirements for special foundations for residential structures, improved drainage facilities, flexible utilities and stronger construction techniques. No significant attempts have been made in the Seal Cove area to reduce the impact of landslide or fault hazards by design, and indeed, to attempt to do so does not seem reasonable. Likewise, attempts to reduce the risk associated with the landslides and faults by controlling these hazardous processes is impractical, if not impossible.

In summary, it is our opinion that the only practical means of reducing the risk associated with landslide and fault hazards is by prudent land use regulations. Any land use policy should balance the risk against the social, economic and environmental cost in order to determine the level of risk acceptable to the community.

#### RECOMMENDATIONS

The following recommendations are presented for consideration by the County in order to establish prudent land use policies within the Seal Cove area. We believe that the recommendations are consistent with the goals and objectives of the Seismic Safety Element of the General Plan, the original recommendations presented in the Leighton report, and the minimum standards for geotechnical reports which were adopted by the County in 1977. However, after careful review by the County these recommendations may be altered to reflect the final expression of the County perception of acceptable risk.

1) Critical Hazards Area - Due to the complexity of the hazardous geologic conditions in the Seal Cove area we recommend that the entire study area be designated as a "Critical Geotechnical Hazards Area." Such a designation would "red flag" the region as an area of high geologic hazards for which special or more detailed geologic and soil investigations (i.e. geotechnical) will be required prior to development. Additionally, such a designation would alert present and future landowners to the hazardous conditions and the potential higher than normal cost of development.

To protect the interest of the County, individual landowners, and local developers geologic and/or soil investigations of appropriate level should be required for all lands within the study area. These investigations will normally exceed the minimum standards adopted by the County and will specifically address the primary geology and hazard of the site in question.

2) Geotechnical Hazards Map - To facilitate the required geologic and/or soil investigations we have prepared a new hazard zonation map for the Seal Cove area. This map is a modification of the original map prepared by Leighton and Associates in 1971 and is based upon new landslide and fault information generated during the present study. The changes from the original zonation map include (1) combining hazard zone 3 and 4, and (2) moving the boundary of hazard zone 1 and 2 to the east. The geotechnical hazard zones have been compiled on the new 200-scale County base map which we believe is a more useful map because it superimposes property boundaries on an orthophotographic base.

The Geotechnical Hazards Map divides the Seal Cove area into three zones on the basis of similar geotechnical hazards or problems. Consequently, the terrain within each zone is considered to have similar potentials and constraints for development. In essence each zone reflects different levels of risk to man and structures.

The physical conditions and the associated risk of the three zones are described on the Geotechnical Hazards Map along with the various levels of geotechnical investigations required to evaluate the particular hazards in each zone. The following section describes the criteria for each hazard zone, defines the associated risk for development in each zone and defines the scope of required geotechnical investigations. It is recommended that the Geotechnical Hazards Map be officially adopted by the County as part of the final land use policy to guide future development in the Seal Cove study area.

**ZONE 1** - Includes all lands located along the western seacliff that are affected by active landslide processes and accelerated seacliff erosion. The position of the erosion boundary of this zone is established by the easternmost extent of active landsliding plus a setback of 50 feet. The setback zone includes lands which lie outside or east of the active landslides but are expected to experience problems in the future (i.e. 50± years).

Risk Assessment - Risk to development in this zone is considered to be extremely high. It is reasonable to conclude that slow progressive landsliding and seacliff retreat will continue, resulting in structural and property damage. This is especially true for structures or utilities located astride active surface breaks. Rapid catastrophic slope failure of the high, steep portion of the seacliff located west of Ocean Boulevard is a clear probability. Such an event could involve the loss of life as well as significant property damage.

The feasibility of reducing the risk to acceptable levels is extremely low.

No additional development should be allowed in this zone.

**ZONE 2** - Includes all lands within a 100-foot wide zone located immediately adjacent to the zone of active landsliding and accelerated seacliff erosion (i.e. Zone 1). The position of the eastern boundary of this zone is established by a 2:1 (i.e. 26½ degrees) projection measured from the base of the high seacliff located west of Ocean Boulevard.

Risk Assessment - Risk to development in this zone is considered to be moderate to high. Eastward progression of active landsliding is difficult to predict with reliable accuracy.

The likelihood of eliminating the risk is very low, however it may be possible to significantly reduce the impact of the hazard by properly designed foundations.

No development should be allowed in this zone until stability is clearly demonstrated by the required geotechnical investigations.

Required Geotechnical Investigation - Engineering geologic investigation by a certified engineering geologist and a soil and foundation engineering investigation by a registered civil engineer, or a combined equivalent of the above.

- Scope of both investigations should be directed toward a detailed evaluation of the potential landslide hazards in this zone. In most cases, landslide studies will require extensive subsurface work in order to provide the necessary technical data to conduct a detailed slope stability analysis. The geotechnical analysis should provide acceptable factors of safety to clearly demonstrate stability before construction is allowed in this zone.

**ZONE 3** - Includes all lands located outside of the areas affected by active or potential landslides.

Risk Assessment - Risk to development in this zone is considered to be low to moderate. The major geologic hazard in this zone is the threat of surface faulting along the master fault trace and several branching fault traces of the Seal Cove fault. These faults are active and capable of producing damaging surface faulting, strong ground shaking and ground failure.

The relative risk associated with poor surface drainage and potentially expansive soils is generally regarded as moderate to locally high.

The feasibility of reducing the risks to acceptable levels in this zone is considered high. This can be accomplished by careful siting of homes away from active faults, using careful structural and foundation design and adequate surface drainage plans. However, it is possible that some residential parcels will be judged unbuildable due to high seismic hazards.

Development should be allowed in this zone on parcels found to be free of hazardous conditions by the required geotechnical investigations.

Required Geotechnical Investigation - Engineering geologic investigation by a certified engineering geologist and a soil and foundation engineering investigation by a registered civil engineer, or a combined equivalent of the above.

- Scope of engineering geologic investigation should address the seismic hazards related to the master and branching traces of the Seal Cove fault. Particular emphasis of the engineering geologic investigations should be placed on the evaluation of possible surface faulting. Investigative techniques within this area will require the use of subsurface trenching and possibly geophysical traverses unless clear evidence is established to show that no active fault crosses the parcel in question.
- The soil and foundation engineering investigation should address, but not necessarily be confined to, the following items: site preparation and grading, surface drainage, and design parameters for residential foundations.

All of the geotechnical investigations should reference this report and the geologic data presented in the Leighton and Associates report of 1971 and the Seismic and Safety Elements of the General Plan of 1976. The geotechnical reports describing the results of these investigations should be reviewed by the County Geologist following the procedure that is currently in practice. The recommendations expressed in the soil and foundation engineering reports and/or the engineering geologic reports should become conditions of any development application.



TECHNICAL REPORT

GEOLOGIC ANALYSIS  
OF THE  
SEAL COVE AREA

County of San Mateo  
California

August 1980





The geologic data and discussions presented in this report should be regarded as updated and reevaluated information taken from the Leighton report and should not be considered to supersede or diminish the importance of their work. Future development in the Seal Cove area should not proceed without reference to both of these reports and the data compiled for the seismic safety element of the County of San Mateo.

#### ACCOMPANYING ILLUSTRATIONS

Geotechnical Hazards Map, 1 inch = 200 feet, Plate 1 Pocket

Index Map, Figure 1

Topographic and Geologic Index Map, Figure 2

Schematic Geologic Cross Section, Figure 3

Mode of Rock Slump Failure, Figure 4

Progressive North to South Failure of Seacliff Region, Figure 5

Progressive Seacliff Erosion, Figure 6

Seal Cove Fault System, Figure 7

## DEVELOPMENT HISTORY

The portion of coastal San Mateo County that is included in this study is a residential section known as Seal Cove which is located in the southern part of the community of Moss Beach (Figure 1). The northern and southern boundaries of the study area are defined by Cypress and Bernal Avenues, respectively, and include all of the residential property located between the Half Moon Bay Airport and the ocean.

The Seal Cove area was subdivided into residential parcels about 1908. The area was subdivided into 2500 square foot lots with roads and improvements (i.e., streets, sidewalks and utilities) without regard for the geologic constraints. In fact, the primary attraction of the Seal Cove area was the presumed relatively low level of risk associated with the setting as compared to the San Francisco region that was devastated during the earthquake of 1906. The existing street alignments and the lot configurations are essentially the same as the original 1908 development plan. Since that time, residential construction has proceeded at a rather slow, piecemeal rate with home construction being limited to parcels of 5000 square feet.

In the late 1960's development in portions of the Seal Cove community was identified by the U.S. Geological Survey as being constrained by high geologic hazards due to active landsliding and accelerated coastal erosion. On the basis of this information, the County of San Mateo placed a building freeze on the Seal Cove area and authorized Leighton and Associates, the County Geologists, to complete a detailed geologic study of the area and to provide the County with guidelines for future development. The geologic study was completed and the final report was accepted by the County in October of 1971. The Leighton report clearly identified the primary geologic constraints of the Seal Cove as landsliding, faulting, and seacliff erosion. In addition, the report identified less severe potential problems associated with poor surface drainage, high ground water, and expansive soils. On the basis of these concerns, the Seal Cove area was divided into four Geologic Hazard Zones that define different levels of relative geologic stability. The description of each zone identifies the primary geologic hazard that constrains development and defined the type of geologic and soil report that would be required prior to residential development. Table 1 outlines the four hazard zones as presented in the Leighton report of October 15, 1971.




FIGURE 1 - INDEX MAP  
 SEAL COVE STUDY AREA  
 COUNTY OF SAN MATEO, CALIFORNIA

ZONAL RATINGS	GEOLOGIC STABILITY RATINGS	MAJOR GEOLOGIC PROBLEM TYPES	NATURE OF FUTURE GEOLOGY AND SOILS REPORTS REQUIRED
1	MOST SEVERE INSTABILITY	LANDSLIDING (RAPID MOVEMENTS LIKELY)	FEASIBILITY OF CORRECTION HIGHLY IMPROBABLE
2	UNSTABLE	PROGRESSIVE LANDSLIDING, EROSIONAL RETREAT OF BLUFFS, HIGH GROUND WATER AND ACTIVE FAULTING	DETAILED SUBSURFACE INVESTIGATIONS WILL BE NECESSARY TO ANALYZE INSTABILITY
3	DEGREE OF INSTABILITY QUESTIONABLE	COMBINATIONS OF THE ABOVE	DETAILED SUBSURFACE INVESTIGATIONS WILL BE NECESSARY TO DETERMINE DEGREE OF STABILITY
4	MOST STABLE	TYPICAL SOILS PROBLEMS (EXPANSIVE SOILS, ETC.); LOCALIZED GEOLOGIC PROBLEMS (SOIL CREEP, ETC.); SEISMIC RESPONSE, ETC.	CONVENTIONAL INVESTIGATIONS WILL PROBABLY BE ADEQUATE

TABLE 1 - GEOLOGIC HAZARD ZONES AS DEFINED BY LEIGHTON AND ASSOCIATES, OCTOBER 15, 1971



In November of 1971 the County accepted the conclusions and recommendations of the Leighton report and imposed a number of building restrictions on the parcels within the four hazard zones. In addition, Leighton and Associates prepared and sent to the County a specified set of guidelines for geologic and soil investigations conducted in the Seal Cove area. On the basis of the new information, the building freeze was lifted but residential development was allowed to proceed only after the necessary geologic and/or soil investigations were satisfactorily completed. The required reports were reviewed by Leighton and Associates on a part-time basis until 1975 when the County retained A. C. Neufeld as the permanent County Geologist.

The present policy regarding geologic and soil reports has been altered slightly from the recommendations of the Leighton report. At present, detailed geologic and soil investigations are required in Geologic Hazard Zones 1 and 2; however, in zones 3 and 4 such investigations are only required when a parcel is located within fifty feet of a mapped fault. Normally, areas located outside of the fifty foot zone do not require any geologic or soil report prior to construction. The adequacy of the geologic and soil report are evaluated by the County Geologist according to the Minimum Standards for Geotechnical Reports adopted by the County and the review procedures developed by the County Geologist. In some cases the County Geologist has imposed stricter and, at times, more reduced standards where local geology or soil data warrant such changes.

Since the suspension of the 1971 building freeze, 16 new homes have been constructed in the study area. These homes are situated within the following Geologic Hazard Zones as defined by Leighton and Associates:

ZONE 1 - Most severe instability	- no development
ZONE 2 - Unstable	- 9 new homes
ZONE 3 - Degree of instability questionable	- 5 new homes
ZONE 4 - Most stable	- 2 new homes

Our evaluation of the locations and conditions of the new homes indicates that the present stability of most homes is good; however, the safety of two of these homes is in question. These homes are situated in Geologic Hazard Zone 2. The specific locations and geologic concerns of these structures are outlined below:

LOCATION

GEOLOGIC PROBLEM

131 La Grande Avenue

Home, deck and patio constructed within several feet of an active landslide scarp

821 Ocean Boulevard

Front portion of home and driveways are situated over an active landslide tension crack

The home on La Grande was constructed east of a major, active landslide scarp that was well documented in the Leighton report, and recognized by the owner's consultants prior to construction. But at the time that the home on Ocean Boulevard was constructed, no surface evidence of landsliding was noted. Apparently the landslide-related surface cracking has extended to this location since the Leighton investigation of 1971. Small incipient surface cracks can be traced from the parcel on Ocean Boulevard to the east under the neighboring parcel where residential damage is more pronounced, and then north across La Grande Avenue to the prominent scarp area located west of 131 La Grande Avenue.

Our analysis of the geologic hazards of the Seal Cove area indicate that the landslide activity is progressing as predicted nearly a decade ago; however, the previously mapped fault pattern appears to be more complex. As a result of our work we have reevaluated the original hazard zones and have altered the positions of some boundaries. Additionally, we have recommended specific changes in the type and scope of future geotechnical investigation in the Seal Cove area.



PHYSICAL PARAMETERS: Topographic, Geologic and Seismic

The Seal Cove area is characterized by a unique set of physical parameters that strongly influence safe development. The physical conditions that have the most influence are those that relate to the topographic, geologic and seismic setting of the study area. The general characteristics of each of the conditions and their associated constraints and potentials for development are described in the following sections.

TOPOGRAPHIC SETTING - The portion of the community of Moss Beach that is included in this investigation is situated at the north end of a prominent northwest-trending ridge (Figures 2 and 3). The ridge extends from Pillar Point on the south to beyond Seal Cove for a distance of approximately two miles. An east-west profile across the ridge is asymmetrical, characterized by a high, near-vertical seacliff along the western side, a nearly flat terrace surface along the top of the ridge, and a gentle, east-facing slope along the eastern border. The average elevation is nearly 100 feet throughout most of the ridge area, but the ridge top rises to approximately 175 feet above sea level south of the study area. Within the immediate residential portion of the study area the topography is relatively flat with a topographic relief of no more than 25 feet.

The present topography of the Seal Cove area and the surrounding ridge is the product of a long history of rather dynamic geologic processes, of which most are still actively modifying the area. These processes include active landsliding, accelerated seacliff erosion and young fault activity. The terrain that is not affected by these hazardous processes have a relatively high potential for safe development. Such areas are within the essentially flat terrace region situated east of Beach Way and Ocean Boulevard.

GEOLOGIC SETTING - The geologic setting of the Seal Cove area is defined by a variety of earth materials, active slope failure processes and a complex fault zone related to the Seal Cove fault system. The following discussion is designed to present a general description of the geologic setting. For a more detailed account, the Geologic Report of Seal Cove-Moss Beach Area, October 15, 1971 by F. Beach Leighton and Associates, should be consulted. Their report presents a large volume of detailed surface and subsurface geologic data in written and illustrative form. The description of the geologic setting included in this report is based on our field mapping and the information presented in the Leighton report.

The primary earth materials in this part of the Seal Cove community can be divided into two dramatically different types of bedrock units which are overlain by two types of

# EXPLANATION

## Earth Materials

## Map Symbols

### SURFICIAL UNITS

**Qls - Landslides**

Rock slumps of surficial  
and bedrock material

**Qt - Marine Terrace**

Unconsolidated gravel,  
sand and silt


### BEDROCK UNITS

**Tp - Purisima formation**


Highly fractured siltstone,  
shale and sandstone

**Kg - Montara Quartz Diorite**

Coarse-grained quartz  
diorite

 Geologic Contact

 Faults

 Landslides




FIGURE 2. TOPOGRAPHIC AND GEOLOGIC INDEX MAP  
 SEAL COVE STUDY AREA  
 COUNTY OF SAN MATEO, CALIFORNIA  
 Scale 1 inch = 2,000 feet

Topographic base map, Montara Mountain and Half Moon Bay Quad-  
 rangles, 7.5 minute. U.S. Geological Survey




FIGURE 3 SCHEMATIC GEOLOGIC CROSS SECTION

SEAL COVE STUDY AREA  
 COUNTY OF SAN MATEO, CALIFORNIA

surficial deposits (Figures 2 and 3). The two bedrock units consist of a relatively fine-grained sequence of sedimentary rocks belonging to the Purisima formation (Tp) and a massive coarse-grained igneous rock of the Montara Quartz Diorite (Kg). These materials make up the bulk of the rock materials that form the prominent ridge topography, however, in most areas the bedrock is covered by the surficial deposits. The surficial materials consist of a sedimentary Marine Terrace deposit (Qt) that blankets all of the nearly flat topography of the study area, and a complex of active landslides deposits (Qls) which are presently destroying large sections of the western seacliff region. The following discussion describes the physical nature of each type of earth material in the Seal Cove area.

Surficial Units - the relatively unconsolidated deposits that overlie the bedrock material.

Landslide (Qls) - The landslide deposits are composed of both the overlying surficial Marine Terrace and the Purisima bedrock materials. The primary type of failure appears to be rock slump with movement concentrated along deep-seated failure planes. The landslides are concentrated in a coastal belt along the western margin of the study area that extends inland as far as 300 to 400 feet.

Marine Terrace (Qt) - These deposits form a blanket-like covering of gravel, sand, and silt that overlies the bedrock units throughout the relatively flat portion of the study area. The thickness ranges from 3 to 4 feet to as much as 40+ feet.

Bedrock Units - the relatively consolidated materials which form the major portion of the ridge and which the surficial units rest.

Purisima formation (Tp) - This unit consists of a thin-bedded, highly fractured, inter-layered sequence of siltstone, shale, and sandstone. The bedrock is exposed along the entire length of the seacliff area and has been encountered in drill holes located approximately 800 feet east of the seacliff area.

Montara Quartz Diorite (Kg) - This bedrock type is not exposed at the surface but has been penetrated in drill holes along the eastern margin of the study area. It consists of deeply-weathered, medium- to coarse-grained quartz diorite.



The most active geologic process now operating in the study area are two distinctly different types of slope failure. They are confined to the seacliff region and include (1) deep-seated landsliding involving large segments of the seacliff, and (2) shallow sloughing and ravelling of the face of the seacliff.

LANDSLIDING - Active, deep-seated landsliding presently is affecting most of the seacliff located along the western margin of the study area. The average height of the seacliff is approximately 100 feet and, in most cases, the entire seacliff is involved in landsliding. The locations of the crowns (i.e. tops) of the landslides vary considerably, but in several places the crowns are located as much as 300 to 400 feet back (i.e. east) of the top of the seacliff, however, the average distance is nearly 250 feet. The depth to the basal slide planes of these landslides is not well known, but from the surface dimensions it is estimated that the depths equal or exceed the height of the seacliff. Thus, the toes (i.e. bottoms) of most of these landslides are near the base of the seacliff and sea level (Figure 4).

Detailed surface mapping and subsurface drill hole data strongly suggest that the mode or style of slope failure can be characterized as (1) progressing from the north to the south and (2) undergoing rotational failure along a concave-upward basal rupture surface. The north-to-south progressive failure is revealed by the pattern and dimension of the surface breaks noted along the crowns of the individual landslides (Figure 5). For example, the eastern limits of the landslides are commonly defined by one or more landslide-related geomorphic features including prominent crown scarps, trenches (i.e. grabens), linear depressions and tension cracks. The pattern of failure normally starts with a well-developed headwall scarp near the crown of a major landslide block. The scarps commonly are more prominent and better developed along their northern extensions. Most can be traced to the south along somewhat discontinuous curvilinear paths, but the scarps frequently diminishes in height to the south and eventually are replaced by shallow linear depressions or a series of tension cracks. Consequently, it appears that most of the landslide headwall scarps propagate slowly to the south from their points of initiation, following a scissor-like pattern with greater surface displacements being concentrated along the northern extension of the headwall scarps.

Although the basal rupture surfaces for most of the landslides is not well defined, they appear to be controlled structurally by the orientation and the spacing of the bedrock fractures. The stratification of the bedrock is inclined into the seacliff. Such an orientation usually accounts for increased slope stability, but the highly fractured nature of the bedrock and the presence of a prominent set of west-dipping continuous fractures reduce the strength of the bedrock and controls the mode of failure.




FIGURE 4 MODE OF ROCK SUMP FAILURE  
SCHEMATIC CROSS SECTION

SEAL COVE STUDY AREA  
COUNTY OF SAN MATEO, CALIFORNIA




FIGURE 5 PROGRESSIVE NORTH TO SOUTH  
FAILURE OF SEA CLIFF REGION

SEAL COVE STUDY AREA  
COUNTY OF SAN MATEO, CALIFORNIA


Thus when the relatively incompetent bedrock is exposed in a high, near-vertical seacliff that has been oversteepened by wave erosion, the rock becomes detached along the planar surfaces of the fractures. Consequently the seacliff fails in a type of landslide known as a rock slump (Varnes 1978) which normally involves bedrock materials that fail by rotation along a curved basal rupture surface.

The rate at which these large deep-seated landslide masses are failing can be estimated roughly by noting the increase in the scarp heights and in the length of extensions of the tension cracks since the completion of the original landslide mapping in 1971 (i.e. Leighton and Associates). Our measurements indicate that the rate of failure probably is approximately 1 to 3 inches per year; thus the rate of movement is regarded as very slow. However, the possibility of accelerated movements is considered high in many local areas within the presently failing landslide complex.


SLOUGHING - The most active form of slope failure along the seacliff is shallow, small-scale sloughing and ravelling of the face of the cliff. This process is initiated by wave erosion concentrated along the base of the seacliff (Figure 6). This erosional process causes the base of the seacliff to become undercut and locally unstable. The face of the seacliff responds to the oversteepened condition by localized piecemeal sloughing and ravelling. Most of the cliff retreat takes place during the winter season when storm waves vigorously erode and undercut the base of the seacliff. The weak, highly fractured siltstone and shale bedrock and the unconsolidated cover of marine terrace material are left in an oversteepened and unsupported condition, and consequently fail. The fallen debris temporarily protects the base of the cliff, but the waves eventually remove the debris and the oversteepening process starts anew.

An analysis of aerial and ground photographs taken over a period of fifty years, 1926 to 1976, and map extending back approximately 130 years reveals that the average rate of cliff retreat within the study area is now approximately 3 to 4 feet per year. However, this process is episodic and is controlled by a variety of local geologic conditions, thus the average rate cannot be projected into the future with any degree of certainty. For example, using this rate, it would be unreasonable to predict that the top of the seacliff will be located 30 to 40 feet east of its present location by 1990; there may be only 5 feet of cliff retreat in the next ten years, but 55 feet of retreat may occur the subsequent decade. Thus the average rate over a 20 year period would approximate 3 feet per year.


In conclusion, the seacliff portion of the Seal Cove area presently is failing by large deep-seated landsliding and small scale localized sloughing. Although both of these types of failures are partially induced by the oversteepening process



**Stage 1 - Relatively Stable Seacliff**



**Stage 2 - Local instability due to undercutting of base of seacliff**



**Stage 3 - Relative stability attained by piecemeal sloughing and raveling**

**FIGURE 6 PROGRESSIVE SEACLIFF EROSION  
SCHEMATIC DRAWINGS**

SEAL COVE STUDY AREA  
COUNTY OF SAN MATEO, CALIFORNIA

of wave erosion, they are dramatically different in scale and mode of failure. Likewise each presents a very different level of risk to future development.

In our judgment, attempts to control or reduce these hazards by engineering design would not be feasible. The scale of the large active landslides make any stabilization scheme essentially uneconomical, likewise an engineering solution needed to stop the erosional activity at the base of the seacliff would severely impact the James V. Fitzgerald Marine Reserve which includes the Seal Cove surface zone. Consequently it appears the most prudent way to reduce the risk is to avoid the areas that are vulnerable to these slope failure hazards.

SEISMIC SETTING - The principal structural feature within the study area is the Seal Cove fault zone and a number of subsidiary branch faults (Figure 7). The master trace of the fault appears to lie near the base of the east-facing slope which forms the eastern boundary of the study area. Here the master trace is considered to be within a zone of pulverized rock that is approximately 100 feet wide. West of this main zone, the location and character of faulting are less well understood. In this region at least three branch faults extend to the southeast from the main Seal Cove fault zone and pass through the study area (Leighton 1971). Subsequent site-specific geologic studies have confirmed with slight modifications the location of some of these branch fault traces. In addition, the analysis of aerial photographs conducted for this study and by A. C. Neufeld, San Mateo County Geologist, strongly indicate that several additional fault-related lineations cross the relatively undeveloped area located south of San Lucas Avenue.

These branch faults, like those in the main fault zone are considered to be normal faults characterized primarily by vertical displacements. The main fault trace is identified as the zone of greatest concentration of displacement. Indeed the east-facing slope that forms the eastern boundary of the study area is considered to be a fault scarp produced by displacement along the main trace of the Seal Cove fault. Although the branch faults also are considered to be active traces, both the surface expressions of these faults and the subsurface data presented by the Leighton report indicate that the amount of displacement and the state of activity along these faults probably is much less than the master trace.

Recent fault studies suggest that the Seal Cove fault zone is a segment of a major coastal boundary fault zone that merges with the San Andreas fault north of San Francisco (Greene and others, 1973; Weber and Cotton, 1980). This fault zone includes the Seal Cove, San Gregorio, Sur, San Simeon and Hosgri faults and extends to the south for more than 260 miles to the vicinity of Point Arguello. The largest historic seismic event recorded along the San Gregorio fault system




FIGURE 7 SEAL COVE FAULT SYSTEM


SEAL COVE STUDY AREA  
COUNTY OF SAN MATEO, CALIFORNIA

were two Richter magnitude 6.1 earthquakes which occurred within one hour of each other near the center of Monterey Bay in 1926. Studies of historic seismicity along the San Gregorio fault zone in the vicinity of Monterey Bay indicate that the fault zone probably is capable of producing an earthquake of Richter magnitude 7.2 - 7.9. Paleoseismologic research on the San Gregorio fault zone near Point Ano Nuevo, in San Mateo County, suggests that (1) earthquakes of Richter magnitude 7.6 - 7.7, and possibly greater than Richter magnitude 8.0, have occurred along the San Gregorio fault zone in the past and are anticipated to occur in the future, and (2) a reasonable estimate of the recurrence interval for major earthquakes (M 7.5) along the San Gregorio fault system is 225-400 years and probably is about 300-325 years (Weber and Cotton, 1980). Since the Seal Cove fault is considered to be an extension of the San Gregorio fault system, it is reasonable to attribute a similar level of seismic activity to the Seal Cove area.

In conclusion, the main trace and the branching traces of the Seal Cove fault are considered to be active. The branching faults located in the relatively undeveloped area south of San Lucas Avenue are only approximately located. Indeed, there may be additional fault strands that are as yet unrecognized in this region. Should a major earthquake take place along the Seal Cove fault the anticipated seismic hazards would be severe ground shaking, surface faulting along the master trace and branching fault traces and ground failure (landsliding, sloughing, settlement, etc.). The risk associated with these hazards can be dramatically reduced by carefully siting homes away from active fault traces or potential zones of ground failure and by careful structural and foundation design.







SEAL COVE  
GEOLOGICAL HAZARDS ZONES



RESOLUTION NO. \_\_\_\_\_

**RESOLUTION OF THE MONTARA WATER AND SANITARY DISTRICT  
DECLARING EXISTENCE OF EMERGENCY CONDITION REQUIRING  
IMMEDIATE EXPENDITURE OF FUNDS AND OTHER ACTIONS IN  
FURTHERANCE OF PUBLIC HEALTH, WELFARE AND SAFETY, AND  
APPROVING AND RATIFYING EXECUTION OF CONTRACTS FOR  
REPAIR OF ESSENTIAL PUBLIC FACILITIES RELATING THERETO  
(Seal Cove Critical Geotechnical Hazards Area)**

**BE IT RESOLVED BY THE BOARD OF THE MONTARA WATER AND  
SANITARY DISTRICT, A PUBLIC AGENCY IN THE COUNTY OF SAN  
MATEO, CALIFORNIA, AS FOLLOWS:**

1. **Findings.** This Board finds and determines as follows:
  - a. On or about March 16, 2025, Montara Water and Sanitary District (District or MWSD) staff was alerted to active land movement along the coastal bluff in the Seal Cove Critical Geotechnical Hazards Area (Area), including sinkholes, causing a series of line breaks and water leaks of MWSD infrastructure located within portions of public roads, including San Lucas Avenue, west of Del Mar Avenue, Ocean Avenue between San Lucas and Madrone, La Grande Avenue, Los Banos Avenue, as well as the Park Street and Beach Street intersection. Additionally, since mid-February, staff has responded to ten (10) water leaks and repaired eight (8) leaks on either a District water main or individual property water connections near San Lucas Avenue and Ocean Boulevard.
  - b. The Area lies along the Seal Cove earthquake fault line and numerous branch lines which are considered to be active and has long been designated by the County of San Mateo as a Geotechnical Hazard Area with low coastal cliff stability. The Area has been extensively studied with regard to geotechnical and natural hazards that subject it to active landslides, seismic hazards, sea cliff erosion and sea level rise. A 1980 study identified four (4) Geotech zones (attached as Exhibit A is the Geologic Hazard Zone Map) that is currently used by San Mateo County, the local agency with land use authority, as the guide for development in the Seal Cove area.
  - c. MWSD staff – who are on call 24 hours a day to repair leaks – took quick action to fix these leaks and also relocate water connections for one (1) home, and above ground for two (2) homes on San Lucas. Above ground connections are a safer means to provide water when land movement can continue to cause leaks.

RESOLUTION NO. \_\_\_\_\_

**RESOLUTION OF THE MONTARA WATER AND SANITARY DISTRICT  
DECLARING EXISTENCE OF EMERGENCY CONDITION REQUIRING  
IMMEDIATE EXPENDITURE OF FUNDS AND OTHER ACTIONS IN  
FURTHERANCE OF PUBLIC HEALTH, WELFARE AND SAFETY, AND  
APPROVING AND RATIFYING EXECUTION OF CONTRACTS FOR  
REPAIR OF ESSENTIAL PUBLIC FACILITIES RELATING THERETO  
(Seal Cove Critical Geotechnical Hazards Area)**

Staff are working to further protect the District's water and sewer infrastructure in the Area to reduce the potential for any further water or sewage leaks. Staff additionally tested and visually inspected District sewers to confirm no breaks that would allow untreated sewage into the soils or coastal environment.

- d. The water main in San Lucas has been capped at the western side of the Del Mar intersection. District staff have rerouted the water main mid-block on San Lucas west of Del Mar to maintain water supply to the fire hydrant at this intersection, and to connect into the water main on Del Mar.
- e. To restore service to two (2) homes on San Lucas (86 and 89 San Lucas Avenue), District staff have assisted in providing above ground water service connections between the affected properties and either an adjacent neighboring property willing to allow the hose bib connection or via the District's water mains on San Lucas or Del Mar. These above ground connections provide a safer water service connection by providing the property owners visual access to their water service line, eliminates the need for District or contractor staff to excavate in unstable soils, and reduces the risk to District infrastructure.
- f. San Mateo County previously closed San Lucas Avenue from Del Mar Avenue to Ocean Boulevard and will not allow excavation permits for any District work in this closed area.
- g. The District is working to rapidly review existing geotechnical reports to determine the safest location for District assets. The District is examining the need to cap or relocate additional water mains and sewer mains outside of the geologic hazard zones. This may require customers to relocate their water connections and for some properties to maintain above ground water connections.
- h. Due to the unstable nature of land within the Area and the urgent need to repair or abandon lines and other facilities, following competitive bidding procedures would and will endanger and adversely affect public health, welfare and safety because of the delay's attendant thereon.
- i. The public interest and necessity demand the immediate expenditure of District funds to accomplish emergency work in order to safeguard life, health and property.

RESOLUTION NO. \_\_\_\_\_

**RESOLUTION OF THE MONTARA WATER AND SANITARY DISTRICT  
DECLARING EXISTENCE OF EMERGENCY CONDITION REQUIRING  
IMMEDIATE EXPENDITURE OF FUNDS AND OTHER ACTIONS IN  
FURTHERANCE OF PUBLIC HEALTH, WELFARE AND SAFETY, AND  
APPROVING AND RATIFYING EXECUTION OF CONTRACTS FOR  
REPAIR OF ESSENTIAL PUBLIC FACILITIES RELATING THERETO  
(Seal Cove Critical Geotechnical Hazards Area)**

- 2. Declaration.** This Board hereby determines and declares that the above-described incident constitutes an emergency condition under Public Contract Code Sections 22050 and 20806; that the public health, welfare, safety, interest or necessity required and require the immediate and continuing expenditure of public money without soliciting or advertising for bids or receiving the same; that the emergency will not permit delays resulting from competitive solicitation of bids and that the actions taken by the District acting by and through the District Manager to complete the Emergency Work are, and such future actions will be necessary to respond to the emergency.
- 3. Approval, Ratification.** Those certain agreements, task orders, purchase orders or other forms of agreement heretofore entered into by or for the General Manager to accomplish emergency work in the Area are, and each of them is, hereby approved and execution is hereby ratified.
- 4. Authorization.** The General Manager is hereby authorized to enter into such agreements (in form approved by the Attorney for the District) in addition to those hereinabove ratified that are necessary or appropriate to complete emergency work.
- 5. Reports.** The General Manager shall report upon the status of the emergency work and the condition of the emergency at each regular meeting of this Board hereafter until the emergency condition is terminated. This Board shall determine by a four-fifth's vote at each such meeting whether the emergency condition warrants continuation of suspension of competitive bidding.
- 6. Operative Date.** This Resolution shall be effective upon the date of its adoption and is operative retroactively to the date of the first agreement ratified hereby.

\_\_\_\_\_  
President, Montara Water and Sanitary District

COUNTERSIGNED:

\_\_\_\_\_  
Secretary, Montara Water and Sanitary District

RESOLUTION NO. \_\_\_\_\_

**RESOLUTION OF THE MONTARA WATER AND SANITARY DISTRICT  
DECLARING EXISTENCE OF EMERGENCY CONDITION REQUIRING  
IMMEDIATE EXPENDITURE OF FUNDS AND OTHER ACTIONS IN  
FURTHERANCE OF PUBLIC HEALTH, WELFARE AND SAFETY, AND  
APPROVING AND RATIFYING EXECUTION OF CONTRACTS FOR  
REPAIR OF ESSENTIAL PUBLIC FACILITIES RELATING THERETO  
(Seal Cove Critical Geotechnical Hazards Area)**

\* \* \* \*

I HEREBY CERTIFY that the foregoing Resolution No. \_\_\_\_\_ duly and regularly adopted and passed by the Board of the Montara Water and Sanitary District, County of San Mateo, California, at a Special Adjourned Meeting thereof held on the 27<sup>th</sup> day of March 2025, by the following vote:

AYES, Directors:

ABSTENTION:

NOES, Directors:

ABSENT, Directors:

---

Secretary, Montara Water and Sanitary District




# Geologic Analysis of the Seal Cove Area

## EXHIBIT A

### GEOTECHNICAL HAZARDS MAP SEAL COVE STUDY AREA

PLATE NO. 1 SCALE: 1"=200' DATE: 8/5/80  
 PROJECT NO. G 112-80 GEO./ENG. BY: W.C. APPROVED BY: WRC


#### GEOTECHNICAL HAZARDS MAP



#### EXPLANATION

GEOTECHNICAL HAZARD ZONE	RISK ASSESSMENT	REQUIRED GEOTECHNICAL INVESTIGATION
<b>ZONE 1</b> ■ Includes all lands located along the western seaciff that are adversely affected by active landslide processes and accelerated seaciff erosion. The position of the eastern boundary of this zone is established by the easternmost extent of active landsliding plus a setback of 50 feet. The setback zone includes lands which lie outside or east of the active landslides but are expected to experience problems in the future (i.e. 502 years).	<b>UNSTABLE</b> ■ Risk to development in this zone is considered to be extremely high. It is reasonable to conclude that slow progressive landsliding and seaciff retreat will continue, resulting in structural and property damage. This is especially true for structures or utilities located astride active surface breaks. Rapid catastrophic slope failure of the high, steep portion of the seaciff located west of Ocean Boulevard is a clear probability. Such an event could involve the loss of life as well as significant property damage. The feasibility of reducing the risk to acceptable levels is extremely low. ★ No additional development should be allowed in this zone.	■ No investigation deemed feasible due to the severity of the instability.
<b>ZONE 2</b> ■ Includes all lands within a 100-foot wide zone located immediately adjacent to the zone of active landsliding and accelerated seaciff erosion (i.e. Zone 1). The position of the eastern boundary of this zone is established in part by an approximate 2:1 (i.e. 261 degrees) projection measured from the base of the high seaciff located west of Ocean Boulevard.	<b>QUESTIONABLE STABILITY</b> ■ Risk to development in this zone is considered to be moderate to high. Eastward progression of active landsliding is difficult to predict with reliable accuracy. The likelihood of eliminating the risk is very low, however it may be possible to significantly reduce the impact of the hazard by properly designed foundations. ★ No development should be allowed in this zone until stability is clearly demonstrated by the required geotechnical investigations.	■ Engineering geologic investigation by a certified engineering geologist and a soil and foundation engineering investigation by a registered civil engineer, or a combined equivalent of the above. • Scope of both investigations should be directed toward a detailed evaluation of the potential landslide hazards in this zone. In most cases, landslide studies will require extensive subsurface work in order to provide the necessary technical data to conduct a detailed slope stability analysis. The geotechnical analysis should provide acceptable factors of safety to clearly demonstrate stability before construction is allowed in this zone.
<b>ZONE 3</b> ■ Includes all lands located outside of the areas affected by active or potential landslides.	<b>MOST STABLE</b> ■ Risk to development in this zone is considered to be low to moderate. The major geologic hazard in this zone is the threat of surface faulting along the master fault trace and several branching fault traces of the Seal Cove fault. These faults are active and capable of producing damaging surface faulting, strong ground shaking and ground failure. The relative risk associated with poor surface drainage and potentially expansive soils is generally regarded as moderate to locally high. The feasibility of reducing the risks to acceptable levels in this zone is considered high. This can be accomplished by careful siting of homes away from active faults, using careful structural and foundation design and adequate surface drainage plans. However, it is possible that some residential parcels will be judged unbuildable due to high seismic hazards. ★ Development should be allowed in this zone on parcels found to be free of hazardous conditions by the required geotechnical investigations.	■ Engineering geologic investigation by a certified engineering geologist and a soil and foundation engineering investigation by a registered civil engineer, or a combined equivalent of the above, unless evidence is available to show that such investigations are not required. • Scope of engineering geologic investigation should address the seismic hazards related to the master and branching traces of the Seal Cove fault. Particular emphasis of the engineering geologic investigations should be placed on the evaluation of possible surface faulting. Investigative techniques within this area will require the use of subsurface trenching and possibly geophysical traverses unless clear evidence is established to show that no active fault crosses the parcel in question. • The soil and foundation engineering investigation should address, but not necessarily be confined to, the following items: site preparation and grading, surface drainage, and design parameters for residential foundations.

#### MAP SYMBOLS



#### NOTES TO USERS

■ This map provides geotechnical data based on detailed surface mapping, interpretation of aerial photographs and the geologic data presented in the report entitled *Geologic Report of Seal Cove - Moss Beach Area*, October 15, 1971 by F. Beach Leighton and Associates. The map is primarily designed for use by geologists, engineers and planners and is not intended to be a substitute for detailed site specific geotechnical investigations.  
 Additional description and explanation of the geologic conditions of the Seal Cove study area may be found in the accompanying report entitled *Geologic Analysis of the Seal Cove Area, County of San Mateo*, August 5, 1980 by William Cotton and Associates.



GEOLOGIC ANALYSIS  
OF THE  
SEAL COVE AREA  
COUNTY OF SAN MATEO

100-1000  
1000-1000  
1000-1000  
1000-1000





William Cotton  
and Associates

GEOTECHNICAL CONSULTANTS

314 Tait Avenue, Lbs Gatos, California 95030  
(408) 354-5542

David C. Hale, Director  
Planning Department  
County of San Mateo  
590 Hamilton Street  
Redwood City, California 94063

August 5, 1980  
G112-80

Dear Mr. Hale:

In accordance with our agreement with the County of San Mateo (#5500-80-426) dated July 14, 1980, the final geologic report is hereby submitted.

As a result of our work, the original Geologic Map of the Seal Cove area has been updated and a number of recommendations are presented herein in order to help strengthen the present land use policies that control development.

Our report is presented in two basic parts consisting of a Conclusions and Recommendations section followed by a Technical Report section. The technical report describes the geologic data and analysis that we used to support the final conclusions and recommendations.

It has been our pleasure to be of service to the County on this interesting project. If we can be of help in clarifying any aspect of this report, please do not hesitate to contact our office.

Sincerely yours,

WILLIAM COTTON AND ASSOCIATES

William R. Cotton  
Engineering Geologist, CEG 882

bp

Attached report



CONCLUSIONS  
AND  
RECOMMENDATIONS

GEOLOGIC  
ANALYSIS  
OF THE  
SEAL COVE AREA

COUNTY OF SAN MATEO  
CALIFORNIA

August 1980



## CONCLUSIONS

The Seal Cove study area is exposed to a variety of geologic hazards that severely affect future land use decisions. These conditions and the level of associated risk were well documented nearly a decade ago by a County-authorized geologic study conducted by Leighton and Associates (October 1971). The present study was designed to update the geologic information presented in the Leighton report and to reevaluate the residential development regulations.

The following geologic hazards are the principal geologic concerns of the Seal Cove area:

Landsliding - Deep-seated landslides presently are destroying extensive sections of the seacliff region which define the western edge of the study area. Approximately 17 homes have suffered some form of structural damage due to landslide activity. The inland extent of the active landsliding from the coastline ranges between 100 to 400 feet; however, the average distance is nearly 250 feet. The average rate of landslide movement is very slow, probably ranging between 1 and 3 inches per year. However, the probability of accelerated movements is considered high in many local areas within the presently failing landslide complex. This is especially true of the high seacliff area located west of Ocean Boulevard where rapid catastrophic failure is a clear possibility.

Faulting - The active Seal Cove fault and a number of branching fault traces pass through the study area. The main trace is confined to a 100-foot-wide zone located along the eastern margin of the study area. Although most of this zone lies outside of the study area, the branching fault traces pass through the main portion of the residential area. All of these faults are considered to be active, and thus, capable of generating earthquakes with associated ground shaking, surface faulting and ground failure.

Seacliff Erosion - The entire coastline area presently is experiencing severe erosion by wave activity. This erosion process causes the seacliff to become undercut at its base and locally unstable. The oversteepened face of the seacliff responds by shallow, piecemeal sloughing; however, natural stability is never achieved due to the constant erosional activity within the surf zone. The result is a systematic retreat of the seacliff by local episodic sloughing. The average rate of cliff retreat is approximately 3 to 4 feet per year in the Seal Cove area.

A number of additional geologic problems have been identified in the Seal Cove area; however, these are

relatively minor hazards when compared to those outlined above and can be significantly mitigated by design. These problems include potentially expansive soils, poor surface drainage and problems associated with shallow ground water.

### RISK ANALYSIS

The development of sound public policy to deal with the geologic hazards of the Seal Cove area requires an answer to the question, "How safe is safe enough?" The information and analysis presented in this report is an attempt to provide the necessary framework on which the appropriate County decisionmakers can judge acceptable levels of risk.

To properly assess the appropriate level of risk to the community, a number of important steps are essential. First, and probably most importantly, the presence of geologic hazards must be recognized. In the Seal Cove area, although the original subdivision was initiated in the early 1900's, the hazardous landslide and fault conditions were not recognized until nearly ten years ago. Consequently, many homes and streets were built on active landslides or astride active traces of the Seal Cove fault, and thus, have sustained considerable damage.

The second step in this process takes place after the geologic hazards have been recognized. This step requires detailed studies to determine the physical characteristics of the hazards. For the Seal Cove area, this was accomplished through the initial geologic study conducted by Leighton and Associates in 1971. They identified a large area of active landslides, and a number of fault traces associated with the Seal Cove fault. As an important part of their investigation, they provided a detailed description of the dimensions and level of activity of the landslides and faults.

Once the geologic hazards are recognized and carefully characterized, then the degree or level of risk associated with each hazard can be evaluated. In the Seal Cove area the present land use tends to limit the exposure of risk mainly to utilities, streets and houses; however, the potential for personal injury or loss of life is possible in local areas. The decision as to whether the various levels of risk are tolerable or intolerable to the public requires the input of the County decisionmakers. An important part of any risk analysis is the consideration of possible mitigating measures that could reduce the risk associated with each type of hazard. This kind of action is usually the product of the democratic process and depends as much on social, economic and environmental values as on geologic knowledge. There are a number of mitigating measures that may reduce risk to tolerable levels. For example, land use may be regulated to the degree that residential development is simply restricted from



hazardous areas, thus the hazard is avoided and the risk is essentially eliminated. This has been done in the Seal Cove area by prohibiting construction in active landslide areas, astride active fault traces and close to the edge of the seacliff.

Another method of reducing the risk is by attempting to reduce the impact of the hazard. This might include requirements for special foundations for residential structures, improved drainage facilities, flexible utilities and stronger construction techniques. No significant attempts have been made in the Seal Cove area to reduce the impact of landslide or fault hazards by design, and indeed, to attempt to do so does not seem reasonable. Likewise, attempts to reduce the risk associated with the landslides and faults by controlling these hazardous processes is impractical, if not impossible.

In summary, it is our opinion that the only practical means of reducing the risk associated with landslide and fault hazards is by prudent land use regulations. Any land use policy should balance the risk against the social, economic and environmental cost in order to determine the level of risk acceptable to the community.

#### RECOMMENDATIONS

The following recommendations are presented for consideration by the County in order to establish prudent land use policies within the Seal Cove area. We believe that the recommendations are consistent with the goals and objectives of the Seismic Safety Element of the General Plan, the original recommendations presented in the Leighton report, and the minimum standards for geotechnical reports which were adopted by the County in 1977. However, after careful review by the County these recommendations may be altered to reflect the final expression of the County perception of acceptable risk.

1) Critical Hazards Area - Due to the complexity of the hazardous geologic conditions in the Seal Cove area we recommend that the entire study area be designated as a "Critical Geotechnical Hazards Area." Such a designation would "red flag" the region as an area of high geologic hazards for which special or more detailed geologic and soil investigations (i.e. geotechnical) will be required prior to development. Additionally, such a designation would alert present and future landowners to the hazardous conditions and the potential higher than normal cost of development.

To protect the interest of the County, individual landowners, and local developers geologic and/or soil investigations of appropriate level should be required for all lands within the study area. These investigations will normally exceed the minimum standards adopted by the County and will specifically address the primary geology and hazard of the site in question.

2) Geotechnical Hazards Map - To facilitate the required geologic and/or soil investigations we have prepared a new hazard zonation map for the Seal Cove area. This map is a modification of the original map prepared by Leighton and Associates in 1971 and is based upon new landslide and fault information generated during the present study. The changes from the original zonation map include (1) combining hazard zone 3 and 4, and (2) moving the boundary of hazard zone 1 and 2 to the east. The geotechnical hazard zones have been compiled on the new 200-scale County base map which we believe is a more useful map because it superimposes property boundaries on an orthophotographic base.

The Geotechnical Hazards Map divides the Seal Cove area into three zones on the basis of similar geotechnical hazards or problems. Consequently, the terrain within each zone is considered to have similar potentials and constraints for development. In essence each zone reflects different levels of risk to man and structures.

The physical conditions and the associated risk of the three zones are described on the Geotechnical Hazards Map along with the various levels of geotechnical investigations required to evaluate the particular hazards in each zone. The following section describes the criteria for each hazard zone, defines the associated risk for development in each zone and defines the scope of required geotechnical investigations. It is recommended that the Geotechnical Hazards Map be officially adopted by the County as part of the final land use policy to guide future development in the Seal Cove study area.

**ZONE 1** - Includes all lands located along the western seacliff that are affected by active landslide processes and accelerated seacliff erosion. The position of the erosion boundary of this zone is established by the easternmost extent of active landsliding plus a setback of 50 feet. The setback zone includes lands which lie outside or east of the active landslides but are expected to experience problems in the future (i.e. 50± years).

Risk Assessment - Risk to development in this zone is considered to be extremely high. It is reasonable to conclude that slow progressive landsliding and seacliff retreat will continue, resulting in structural and property damage. This is especially true for structures or utilities located astride active surface breaks. Rapid catastrophic slope failure of the high, steep portion of the seacliff located west of Ocean Boulevard is a clear probability. Such an event could involve the loss of life as well as significant property damage.

The feasibility of reducing the risk to acceptable levels is extremely low.

No additional development should be allowed in this zone.

**ZONE 2** - Includes all lands within a 100-foot wide zone located immediately adjacent to the zone of active landsliding and accelerated seacliff erosion (i.e. Zone 1). The position of the eastern boundary of this zone is established by a 2:1 (i.e. 26½ degrees) projection measured from the base of the high seacliff located west of Ocean Boulevard.

Risk Assessment - Risk to development in this zone is considered to be moderate to high. Eastward progression of active landsliding is difficult to predict with reliable accuracy.

The likelihood of eliminating the risk is very low, however it may be possible to significantly reduce the impact of the hazard by properly designed foundations.

No development should be allowed in this zone until stability is clearly demonstrated by the required geotechnical investigations.

Required Geotechnical Investigation - Engineering geologic investigation by a certified engineering geologist and a soil and foundation engineering investigation by a registered civil engineer, or a combined equivalent of the above.

- Scope of both investigations should be directed toward a detailed evaluation of the potential landslide hazards in this zone. In most cases, landslide studies will require extensive subsurface work in order to provide the necessary technical data to conduct a detailed slope stability analysis. The geotechnical analysis should provide acceptable factors of safety to clearly demonstrate stability before construction is allowed in this zone.

**ZONE 3** - Includes all lands located outside of the areas affected by active or potential landslides.

Risk Assessment - Risk to development in this zone is considered to be low to moderate. The major geologic hazard in this zone is the threat of surface faulting along the master fault trace and several branching fault traces of the Seal Cove fault. These faults are active and capable of producing damaging surface faulting, strong ground shaking and ground failure.

The relative risk associated with poor surface drainage and potentially expansive soils is generally regarded as moderate to locally high.

The feasibility of reducing the risks to acceptable levels in this zone is considered high. This can be accomplished by careful siting of homes away from active faults, using careful structural and foundation design and adequate surface drainage plans. However, it is possible that some residential parcels will be judged unbuildable due to high seismic hazards.

Development should be allowed in this zone on parcels found to be free of hazardous conditions by the required geotechnical investigations.

Required Geotechnical Investigation - Engineering geologic investigation by a certified engineering geologist and a soil and foundation engineering investigation by a registered civil engineer, or a combined equivalent of the above.

- Scope of engineering geologic investigation should address the seismic hazards related to the master and branching traces of the Seal Cove fault. Particular emphasis of the engineering geologic investigations should be placed on the evaluation of possible surface faulting. Investigative techniques within this area will require the use of subsurface trenching and possibly geophysical traverses unless clear evidence is established to show that no active fault crosses the parcel in questions.
- The soil and foundation engineering investigation should address, but not necessarily be confined to, the following items: site preparation and grading, surface drainage, and design parameters for residential foundations.

All of the geotechnical investigations should reference this report and the geologic data presented in the Leighton and Associates report of 1971 and the Seismic and Safety Elements of the General Plan of 1976. The geotechnical reports describing the results of these investigations should be reviewed by the County Geologist following the procedure that is currently in practice. The recommendations expressed in the soil and foundation engineering reports and/or the engineering geologic reports should become conditions of any development application.

TECHNICAL REPORT

GEOLOGIC ANALYSIS  
OF THE  
SEAL COVE AREA

County of San Mateo  
California

August 1980





William Cotton  
and Associates

GEOTECHNICAL CONSULTANTS

314 Tait Avenue, Los Gatos, California 95030  
(408) 354-5542

To: David C. Hale  
Planning Director  
County of San Mateo  
August 5, 1980  
Project G112-80

From: William Cotton and Associates  
Geotechnical Consultants

Subject: Geologic Analysis  
Seal Cove Area  
County of San Mateo, California

INTRODUCTION

At the request of the County of San Mateo we have completed an investigation of the geologic conditions of the Seal Cove area. The primary purpose of our work was to evaluate and update the existing Geologic Map of the area, to identify and characterize the geologic hazards that constrain development, and to evaluate the level of risk associated with the hazardous conditions.

The geologic investigation included the following tasks: (1) detailed geologic surface mapping of the study area at a scale of 1 inch = 200 feet, (2) compilation and analysis of geologic and soil engineering data taken from reports and maps held in the County files, (3) stereoscopic evaluation of sequential aerial photographs, and (4) discussions with area landowners. The equivalent of eight man-days were spent collecting and compiling field data.

In preparing this report we have relied heavily on the following documents:

- Geologic Report of Seal Cove and Moss Beach Area,  
F. Beach Leighton and Associates,  
October 15, 1971.
- Geotechnical Hazards Synthesis Map for  
San Mateo County, Leighton and Associates,  
and San Mateo County Planning Department,  
June 1975.
- Seismic and Safety Elements of the  
General Plan, Vol. 1 and 2; San Mateo  
County Planning Department, December 1976.

The geologic data and discussions presented in this report should be regarded as updated and reevaluated information taken from the Leighton report and should not be considered to supersede or diminish the importance of their work. Future development in the Seal Cove area should not proceed without reference to both of these reports and the data compiled for the seismic safety element of the County of San Mateo.

#### ACCOMPANYING ILLUSTRATIONS

Geotechnical Hazards Map, 1 inch = 200 feet, Plate 1 Pocket

Index Map, Figure 1

Topographic and Geologic Index Map, Figure 2

Schematic Geologic Cross Section, Figure 3

Mode of Rock Slump Failure, Figure 4

Progressive North to South Failure of Seacliff Region, Figure 5

Progressive Seacliff Erosion, Figure 6

Seal Cove Fault System, Figure 7



## DEVELOPMENT HISTORY

The portion of coastal San Mateo County that is included in this study is a residential section known as Seal Cove which is located in the southern part of the community of Moss Beach (Figure 1). The northern and southern boundaries of the study area are defined by Cypress and Bernal Avenues, respectively, and include all of the residential property located between the Half Moon Bay Airport and the ocean.

The Seal Cove area was subdivided into residential parcels about 1908. The area was subdivided into 2500 square foot lots with roads and improvements (i.e., streets, sidewalks and utilities) without regard for the geologic constraints. In fact, the primary attraction of the Seal Cove area was the presumed relatively low level of risk associated with the setting as compared to the San Francisco region that was devastated during the earthquake of 1906. The existing street alignments and the lot configurations are essentially the same as the original 1908 development plan. Since that time, residential construction has proceeded at a rather slow, piecemeal rate with home construction being limited to parcels of 5000 square feet.

In the late 1960's development in portions of the Seal Cove community was identified by the U.S. Geological Survey as being constrained by high geologic hazards due to active landsliding and accelerated coastal erosion. On the basis of this information, the County of San Mateo placed a building freeze on the Seal Cove area and authorized Leighton and Associates, the County Geologists, to complete a detailed geologic study of the area and to provide the County with guidelines for future development. The geologic study was completed and the final report was accepted by the County in October of 1971. The Leighton report clearly identified the primary geologic constraints of the Seal Cove as landsliding, faulting, and seacliff erosion. In addition, the report identified less severe potential problems associated with poor surface drainage, high ground water, and expansive soils. On the basis of these concerns, the Seal Cove area was divided into four Geologic Hazard Zones that define different levels of relative geologic stability. The description of each zone identifies the primary geologic hazard that constrains development and defined the type of geologic and soil report that would be required prior to residential development. Table 1 outlines the four hazard zones as presented in the Leighton report of October 15, 1971.




FIGURE 1 - INDEX MAP  
 SEAL COVE STUDY AREA  
 COUNTY OF SAN MATEO, CALIFORNIA

ZONAL RATINGS	GEOLOGIC STABILITY RATINGS	MAJOR GEOLOGIC PROBLEM TYPES	NATURE OF FUTURE GEOLOGY AND SOILS REPORTS REQUIRED
1	MOST SEVERE INSTABILITY	LANDSLIDING (RAPID MOVEMENTS LIKELY)	FEASIBILITY OF CORRECTION HIGHLY IMPROBABLE
2	UNSTABLE	PROGRESSIVE LANDSLIDING, EROSIONAL RETREAT OF BLUFFS, HIGH GROUND WATER AND ACTIVE FAULTING	DETAILED SUBSURFACE INVESTIGATIONS WILL BE NECESSARY TO ANALYZE INSTABILITY
3	DEGREE OF INSTABILITY QUESTIONABLE	COMBINATIONS OF THE ABOVE	DETAILED SUBSURFACE INVESTIGATIONS WILL BE NECESSARY TO DETERMINE DEGREE OF STABILITY
4	MOST STABLE	TYPICAL SOILS PROBLEMS (EXPANSIVE SOILS, ETC.); LOCALIZED GEOLOGIC PROBLEMS (SOIL CREEP, ETC.); SEISMIC RESPONSE, ETC.	CONVENTIONAL INVESTIGATIONS WILL PROBABLY BE ADEQUATE

TABLE 1 - GEOLOGIC HAZARD ZONES AS DEFINED BY LEIGHTON AND ASSOCIATES, OCTOBER 15, 1971

In November of 1971 the County accepted the conclusions and recommendations of the Leighton report and imposed a number of building restrictions on the parcels within the four hazard zones. In addition, Leighton and Associates prepared and sent to the County a specified set of guidelines for geologic and soil investigations conducted in the Seal Cove area. On the basis of the new information, the building freeze was lifted but residential development was allowed to proceed only after the necessary geologic and/or soil investigations were satisfactorily completed. The required reports were reviewed by Leighton and Associates on a part-time basis until 1975 when the County retained A. C. Neufeld as the permanent County Geologist.

The present policy regarding geologic and soil reports has been altered slightly from the recommendations of the Leighton report. At present, detailed geologic and soil investigations are required in Geologic Hazard Zones 1 and 2; however, in zones 3 and 4 such investigations are only required when a parcel is located within fifty feet of a mapped fault. Normally, areas located outside of the fifty foot zone do not require any geologic or soil report prior to construction. The adequacy of the geologic and soil report are evaluated by the County Geologist according to the Minimum Standards for Geotechnical Reports adopted by the County and the review procedures developed by the County Geologist. In some cases the County Geologist has imposed stricter and, at times, more reduced standards where local geology or soil data warrant such changes.

Since the suspension of the 1971 building freeze, 16 new homes have been constructed in the study area. These homes are situated within the following Geologic Hazard Zones as defined by Leighton and Associates:

ZONE 1 - Most severe instability	- no development
ZONE 2 - Unstable	- 9 new homes
ZONE 3 - Degree of instability questionable	- 5 new homes
ZONE 4 - Most stable	- 2 new homes

Our evaluation of the locations and conditions of the new homes indicates that the present stability of most homes is good; however, the safety of two of these homes is in question. These homes are situated in Geologic Hazard Zone 2. The specific locations and geologic concerns of these structures are outlined below:

LOCATION

GEOLOGIC PROBLEM

131 La Grande Avenue

Home, deck and patio constructed within several feet of an active landslide scarp

821 Ocean Boulevard

Front portion of home and driveways are situated over an active landslide tension crack

The home on La Grande was constructed east of a major, active landslide scarp that was well documented in the Leighton report, and recognized by the owner's consultants prior to construction. But at the time that the home on Ocean Boulevard was constructed, no surface evidence of landsliding was noted. Apparently the landslide-related surface cracking has extended to this location since the Leighton investigation of 1971. Small incipient surface cracks can be traced from the parcel on Ocean Boulevard to the east under the neighboring parcel where residential damage is more pronounced, and then north across La Grande Avenue to the prominent scarp area located west of 131 La Grande Avenue.

Our analysis of the geologic hazards of the Seal Cove area indicate that the landslide activity is progressing as predicted nearly a decade ago; however, the previously mapped fault pattern appears to be more complex. As a result of our work we have reevaluated the original hazard zones and have altered the positions of some boundaries. Additionally, we have recommended specific changes in the type and scope of future geotechnical investigation in the Seal Cove area.



PHYSICAL PARAMETERS: Topographic, Geologic and Seismic

The Seal Cove area is characterized by a unique set of physical parameters that strongly influence safe development. The physical conditions that have the most influence are those that relate to the topographic, geologic and seismic setting of the study area. The general characteristics of each of the conditions and their associated constraints and potentials for development are described in the following sections.

TOPOGRAPHIC SETTING - The portion of the community of Moss Beach that is included in this investigation is situated at the north end of a prominent northwest-trending ridge (Figures 2 and 3). The ridge extends from Pillar Point on the south to beyond Seal Cove for a distance of approximately two miles. An east-west profile across the ridge is asymmetrical, characterized by a high, near-vertical seacliff along the western side, a nearly flat terrace surface along the top of the ridge, and a gentle, east-facing slope along the eastern border. The average elevation is nearly 100 feet throughout most of the ridge area, but the ridge top rises to approximately 175 feet above sea level south of the study area. Within the immediate residential portion of the study area the topography is relatively flat with a topographic relief of no more than 25 feet.

The present topography of the Seal Cove area and the surrounding ridge is the product of a long history of rather dynamic geologic processes, of which most are still actively modifying the area. These processes include active landsliding, accelerated seacliff erosion and young fault activity. The terrain that is not affected by these hazardous processes have a relatively high potential for safe development. Such areas are within the essentially flat terrace region situated east of Beach Way and Ocean Boulevard.

GEOLOGIC SETTING - The geologic setting of the Seal Cove area is defined by a variety of earth materials, active slope failure processes and a complex fault zone related to the Seal Cove fault system. The following discussion is designed to present a general description of the geologic setting. For a more detailed account, the Geologic Report of Seal Cove-Moss Beach Area, October 15, 1971 by F. Beach Leighton and Associates, should be consulted. Their report presents a large volume of detailed surface and subsurface geologic data in written and illustrative form. The description of the geologic setting included in this report is based on our field mapping and the information presented in the Leighton report.

The primary earth materials in this part of the Seal Cove community can be divided into two dramatically different types of bedrock units which are overlain by two types of

# EXPLANATION

## Earth Materials

## Map Symbols

### SURFICIAL UNITS

**Qls - Landslides**

Rock slumps of surficial  
and bedrock material

**Qt - Marine Terrace**

Unconsolidated gravel,  
sand and silt


### BEDROCK UNITS

**Tp - Purisima formation**


Highly fractured siltstone,  
shale and sandstone

**Kg - Montara Quartz Diorite**

Coarse-grained quartz  
diorite

 Geologic Contact

 Faults

 Landslides






FIGURE 2. TOPOGRAPHIC AND GEOLOGIC INDEX MAP  
 SEAL COVE STUDY AREA  
 COUNTY OF SAN MATEO, CALIFORNIA  
 Scale 1 inch = 2,000 feet

Topographic base map, Montara Mountain and Half Moon Bay Quad-  
 rangles, 7.5 minute. U.S. Geological Survey




FIGURE 3 SCHEMATIC GEOLOGIC CROSS SECTION

SEAL COVE STUDY AREA  
 COUNTY OF SAN MATEO, CALIFORNIA

surficial deposits (Figures 2 and 3). The two bedrock units consist of a relatively fine-grained sequence of sedimentary rocks belonging to the Purisima formation (Tp) and a massive coarse-grained igneous rock of the Montara Quartz Diorite (Kg). These materials make up the bulk of the rock materials that form the prominent ridge topography, however, in most areas the bedrock is covered by the surficial deposits. The surficial materials consist of a sedimentary Marine Terrace deposit (Qt) that blankets all of the nearly flat topography of the study area, and a complex of active landslides deposits (Qls) which are presently destroying large sections of the western seacliff region. The following discussion describes the physical nature of each type of earth material in the Seal Cove area.

Surficial Units - the relatively unconsolidated deposits that overlie the bedrock material.

Landslide (Qls) - The landslide deposits are composed of both the overlying surficial Marine Terrace and the Purisima bedrock materials. The primary type of failure appears to be rock slump with movement concentrated along deep-seated failure planes. The landslides are concentrated in a coastal belt along the western margin of the study area that extends inland as far as 300 to 400 feet.

Marine Terrace (Qt) - These deposits form a blanket-like covering of gravel, sand, and silt that overlies the bedrock units throughout the relatively flat portion of the study area. The thickness ranges from 3 to 4 feet to as much as 40+ feet.

Bedrock Units - the relatively consolidated materials which form the major portion of the ridge and which the surficial units rest.

Purisima formation (Tp) - This unit consists of a thin-bedded, highly fractured, inter-layered sequence of siltstone, shale, and sandstone. The bedrock is exposed along the entire length of the seacliff area and has been encountered in drill holes located approximately 800 feet east of the seacliff area.

Montara Quartz Diorite (Kg) - This bedrock type is not exposed at the surface but has been penetrated in drill holes along the eastern margin of the study area. It consists of deeply-weathered, medium- to coarse-grained quartz diorite.

The most active geologic process now operating in the study area are two distinctly different types of slope failure. They are confined to the seacliff region and include (1) deep-seated landsliding involving large segments of the seacliff, and (2) shallow sloughing and ravelling of the face of the seacliff.

LANDSLIDING - Active, deep-seated landsliding presently is affecting most of the seacliff located along the western margin of the study area. The average height of the seacliff is approximately 100 feet and, in most cases, the entire seacliff is involved in landsliding. The locations of the crowns (i.e. tops) of the landslides vary considerably, but in several places the crowns are located as much as 300 to 400 feet back (i.e. east) of the top of the seacliff, however, the average distance is nearly 250 feet. The depth to the basal slide planes of these landslides is not well known, but from the surface dimensions it is estimated that the depths equal or exceed the height of the seacliff. Thus, the toes (i.e. bottoms) of most of these landslides are near the base of the seacliff and sea level (Figure 4).

Detailed surface mapping and subsurface drill hole data strongly suggest that the mode or style of slope failure can be characterized as (1) progressing from the north to the south and (2) undergoing rotational failure along a concave-upward basal rupture surface. The north-to-south progressive failure is revealed by the pattern and dimension of the surface breaks noted along the crowns of the individual landslides (Figure 5). For example, the eastern limits of the landslides are commonly defined by one or more landslide-related geomorphic features including prominent crown scarps, trenches (i.e. grabens), linear depressions and tension cracks. The pattern of failure normally starts with a well-developed headwall scarp near the crown of a major landslide block. The scarps commonly are more prominent and better developed along their northern extensions. Most can be traced to the south along somewhat discontinuous curvilinear paths, but the scarps frequently diminishes in height to the south and eventually are replaced by shallow linear depressions or a series of tension cracks. Consequently, it appears that most of the landslide headwall scarps propagate slowly to the south from their points of initiation, following a scissor-like pattern with greater surface displacements being concentrated along the northern extension of the headwall scarps.

Although the basal rupture surfaces for most of the landslides is not well defined, they appear to be controlled structurally by the orientation and the spacing of the bedrock fractures. The stratification of the bedrock is inclined into the seacliff. Such an orientation usually accounts for increased slope stability, but the highly fractured nature of the bedrock and the presence of a prominent set of west-dipping continuous fractures reduce the strength of the bedrock and controls the mode of failure.




FIGURE 4 MODE OF ROCK SUMP FAILURE  
SCHEMATIC CROSS SECTION

SEAL COVE STUDY AREA  
COUNTY OF SAN MATEO, CALIFORNIA




FIGURE 5 PROGRESSIVE NORTH TO SOUTH  
FAILURE OF SEA CLIFF REGION

SEAL COVE STUDY AREA  
COUNTY OF SAN MATEO, CALIFORNIA


Thus when the relatively incompetent bedrock is exposed in a high, near-vertical seacliff that has been oversteepened by wave erosion, the rock becomes detached along the planar surfaces of the fractures. Consequently the seacliff fails in a type of landslide known as a rock slump (Varnes 1978) which normally involves bedrock materials that fail by rotation along a curved basal rupture surface.

The rate at which these large deep-seated landslide masses are failing can be estimated roughly by noting the increase in the scarp heights and in the length of extensions of the tension cracks since the completion of the original landslide mapping in 1971 (i.e. Leighton and Associates). Our measurements indicate that the rate of failure probably is approximately 1 to 3 inches per year; thus the rate of movement is regarded as very slow. However, the possibility of accelerated movements is considered high in many local areas within the presently failing landslide complex.


SLOUGHING - The most active form of slope failure along the seacliff is shallow, small-scale sloughing and ravelling of the face of the cliff. This process is initiated by wave erosion concentrated along the base of the seacliff (Figure 6). This erosional process causes the base of the seacliff to become undercut and locally unstable. The face of the seacliff responds to the oversteepened condition by localized piecemeal sloughing and ravelling. Most of the cliff retreat takes place during the winter season when storm waves vigorously erode and undercut the base of the seacliff. The weak, highly fractured siltstone and shale bedrock and the unconsolidated cover of marine terrace material are left in an oversteepened and unsupported condition, and consequently fail. The fallen debris temporarily protects the base of the cliff, but the waves eventually remove the debris and the oversteepening process starts anew.

An analysis of aerial and ground photographs taken over a period of fifty years, 1926 to 1976, and map extending back approximately 130 years reveals that the average rate of cliff retreat within the study area is now approximately 3 to 4 feet per year. However, this process is episodic and is controlled by a variety of local geologic conditions, thus the average rate cannot be projected into the future with any degree of certainty. For example, using this rate, it would be unreasonable to predict that the top of the seacliff will be located 30 to 40 feet east of its present location by 1990; there may be only 5 feet of cliff retreat in the next ten years, but 55 feet of retreat may occur the subsequent decade. Thus the average rate over a 20 year period would approximate 3 feet per year.


In conclusion, the seacliff portion of the Seal Cove area presently is failing by large deep-seated landsliding and small scale localized sloughing. Although both of these types of failures are partially induced by the oversteepening process



**Stage 1 - Relatively Stable Seacliff**



**Stage 2 - Local instability due to undercutting of base of seacliff**



**Stage 3 - Relative stability attained by piecemeal sloughing and raveling**

**FIGURE 6 PROGRESSIVE SEACLIFF EROSION  
SCHEMATIC DRAWINGS**

SEAL COVE STUDY AREA  
COUNTY OF SAN MATEO, CALIFORNIA



of wave erosion, they are dramatically different in scale and mode of failure. Likewise each presents a very different level of risk to future development.

In our judgment, attempts to control or reduce these hazards by engineering design would not be feasible. The scale of the large active landslides make any stabilization scheme essentially uneconomical, likewise an engineering solution needed to stop the erosional activity at the base of the seacliff would severely impact the James V. Fitzgerald Marine Reserve which includes the Seal Cove surface zone. Consequently it appears the most prudent way to reduce the risk is to avoid the areas that are vulnerable to these slope failure hazards.

SEISMIC SETTING - The principal structural feature within the study area is the Seal Cove fault zone and a number of subsidiary branch faults (Figure 7). The master trace of the fault appears to lie near the base of the east-facing slope which forms the eastern boundary of the study area. Here the master trace is considered to be within a zone of pulverized rock that is approximately 100 feet wide. West of this main zone, the location and character of faulting are less well understood. In this region at least three branch faults extend to the southeast from the main Seal Cove fault zone and pass through the study area (Leighton 1971). Subsequent site-specific geologic studies have confirmed with slight modifications the location of some of these branch fault traces. In addition, the analysis of aerial photographs conducted for this study and by A. C. Neufeld, San Mateo County Geologist, strongly indicate that several additional fault-related lineations cross the relatively undeveloped area located south of San Lucas Avenue.

These branch faults, like those in the main fault zone are considered to be normal faults characterized primarily by vertical displacements. The main fault trace is identified as the zone of greatest concentration of displacement. Indeed the east-facing slope that forms the eastern boundary of the study area is considered to be a fault scarp produced by displacement along the main trace of the Seal Cove fault. Although the branch faults also are considered to be active traces, both the surface expressions of these faults and the subsurface data presented by the Leighton report indicate that the amount of displacement and the state of activity along these faults probably is much less than the master trace.

Recent fault studies suggest that the Seal Cove fault zone is a segment of a major coastal boundary fault zone that merges with the San Andreas fault north of San Francisco (Greene and others, 1973; Weber and Cotton, 1980). This fault zone includes the Seal Cove, San Gregorio, Sur, San Simeon and Hosgri faults and extends to the south for more than 260 miles to the vicinity of Point Arguello. The largest historic seismic event recorded along the San Gregorio fault system





FIGURE 7 SEAL COVE FAULT SYSTEM

SEAL COVE STUDY AREA  
COUNTY OF SAN MATEO, CALIFORNIA

were two Richter magnitude 6.1 earthquakes which occurred within one hour of each other near the center of Monterey Bay in 1926. Studies of historic seismicity along the San Gregorio fault zone in the vicinity of Monterey Bay indicate that the fault zone probably is capable of producing an earthquake of Richter magnitude 7.2 - 7.9. Paleoseismologic research on the San Gregorio fault zone near Point Ano Nuevo, in San Mateo County, suggests that (1) earthquakes of Richter magnitude 7.6 - 7.7, and possibly greater than Richter magnitude 8.0, have occurred along the San Gregorio fault zone in the past and are anticipated to occur in the future, and (2) a reasonable estimate of the recurrence interval for major earthquakes (M 7.5) along the San Gregorio fault system is 225-400 years and probably is about 300-325 years (Weber and Cotton, 1980). Since the Seal Cove fault is considered to be an extension of the San Gregorio fault system, it is reasonable to attribute a similar level of seismic activity to the Seal Cove area.

In conclusion, the main trace and the branching traces of the Seal Cove fault are considered to be active. The branching faults located in the relatively undeveloped area south of San Lucas Avenue are only approximately located. Indeed, there may be additional fault strands that are as yet unrecognized in this region. Should a major earthquake take place along the Seal Cove fault the anticipated seismic hazards would be severe ground shaking, surface faulting along the master trace and branching fault traces and ground failure (landsliding, sloughing, settlement, etc.). The risk associated with these hazards can be dramatically reduced by carefully siting homes away from active fault traces or potential zones of ground failure and by careful structural and foundation design.





SEAL COVE  
GEOLOGICAL HAZARDS ZONES



**ORDINANCE NO. \_\_\_\_**

**INTERIM URGENCY ORDINANCE OF THE BOARD OF DIRECTORS  
OF THE MONTARA WATER AND SANITARY DISTRICT  
TEMPORARILY SUSPENDING THE ISSUANCE OF WATER AND  
SEWER SERVICE PERMITS OR OTHERWISE RESTRICTING SAID  
SERVICE WITHIN THE SEAL COVE CRITICAL GEOLTECNICAL  
HAZARDS AREA**

**WHEREAS**, the Montara Water and Sanitary District (“District or MWSD”) is a Sanitary District duly organized under the Sanitary District Act of 1923 (Health & Safety Code §§ 6400 – 6830) and a public agency formed as a special district and authorized under California law, by a special election of August 11, 1992 and MWSD Resolution 978 to exercise all powers of a county water district in the same manner as county water districts formed under the County Water District Law (Division 12 (commencing with Section 30000) of the Water Code) and authorized to exercise its powers to take appropriate measures and actions to prevent or mitigate an emergency necessary to protect the public safety, health and environment and respond to infrastructure threats; and

**WHEREAS**, on or about March 16 2025, the District was alerted to active land movement along the coastal bluff in the Seal Cove Critical Geotechnical Hazards Area (“Area or Seal Cove Area”), including sinkholes, causing a series of line breaks and water leaks of MWSD infrastructure located within portions of public roads, including San Lucas Avenue, west of Del Mar Avenue, Ocean Avenue between San Lucas and Madrone, La Grande Avenue, Los Banos Avenue, as well as the Park Street and Beach Street intersection; additionally, since mid-February, staff has responded to ten (10) water leaks and repaired eight (8) leaks on either a District water main or individual property water connections near San Lucas Avenue and Ocean Boulevard; and

**WHEREAS**, the Area lies along the Seal Cove earthquake fault line and numerous branch lines which are considered to be active and has long been designated by the County of San Mateo as a Geotechnical Hazard Area with low coastal cliff stability. The Area has been extensively studied regarding geotechnical and natural hazards that subject it to active landslides, seismic hazards, sea cliff erosion and sea level rise. A 1980 study identified four (4) Geotech zones (attached as Exhibit A is the Geologic Hazard Zone Study and Map) currently used by San Mateo County, the local agency with land use authority, as the guide for development in the Seal Cove Area; and

**WHEREAS**, the ongoing land movement and cliffside instability in the Area and portions of MWSD’s service area threatens the integrity of sewer and water supply lines and mains, increasing the risk of line breaks, sewage overflows, water loss, service interruptions and potential contamination of the District’s water supply, including groundwater and coastal waters, making it unsafe to extend water and sewer service to properties in the Areas; and

**ORDINANCE NO. \_\_\_\_**

**INTERIM URGENCY ORDINANCE OF THE BOARD OF DIRECTORS  
OF THE MONTARA WATER AND SANITARY DISTRICT  
TEMPORARILY SUSPENDING THE ISSUANCE OF WATER AND  
SEWER SERVICE PERMITS OR OTHERWISE RESTRICTING SAID  
SERVICE WITHIN THE SEAL COVE CRITICAL GEOLTECNICAL  
HAZARDS AREA**

**WHEREAS**, MWSD's infrastructure in unstable areas is not designed to withstand ongoing ground movement, and new connections could exacerbate system failures and costly emergency repairs. Further, increased development in unstable areas would place excessive strain on MWSD's system, jeopardizing service reliability for existing customers. MWSD must prioritize infrastructure stabilization and maintenance over continued use or expansion in high-risk areas; and

**WHEREAS**, the purpose of this ordinance is to immediately suspend the issuance of new water and sewer permits and/or restrict or discontinue service, including abandonment of District facilities, within the Seal Cove Area due to active land movement, seismic risks, and coastal erosion in order to prevent imminent threats to public health, safety, and infrastructure stability; such action is justified because delaying this ordinance would allow for continued issuance of permits, further increasing risks to public health and infrastructure stability; and

**WHEREAS**, under Health & Safety Code §§ 6512, 6512.7, 6518, 6520, 6521 and 6522, MWSD has authority to regulate, restrict, and prohibit new sewer connections when necessary to protect public health and system integrity. Under Water Code §§ 31020 and 31021, MWSD has the authority to regulate and limit new water connections when necessary to protect the long-term stability of the water supply.

**NOW, THEREFORE, THE BOARD OF THE MONTARA WATER AND SANITARY DISTRICT, A PUBLIC AGENCY IN THE COUNTY OF SAN MATEO, CALIFORNIA, DOES ORDAIN AS FOLLOWS:**

**SECTION 1.** The above recitals are true and correct and incorporated into these findings. Further incorporated into these findings is the District's staff report in support of emergency actions related to the Seal Cove Critical Geotechnical Hazards Area considered by the District's Board of Directors at a special meeting convened on March 27, 2025.

**SECTION 2.** Effective immediately, MWSD shall not accept applications for service nor issue new water or sewer permits for properties located within the Area, as defined in Exhibit A, nor allow the reactivation of inactive service or other actions that, in the opinion of the District's General Manager and/or the District's Water and Sewer Engineers, are necessary to protect the District's critical infrastructure, including the imposition of service conditions related to both District owned facilities and privately owned facilities, and that the District is not responsible for maintenance



**ORDINANCE NO. \_\_\_\_**

**INTERIM URGENCY ORDINANCE OF THE BOARD OF DIRECTORS  
OF THE MONTARA WATER AND SANITARY DISTRICT  
TEMPORARILY SUSPENDING THE ISSUANCE OF WATER AND  
SEWER SERVICE PERMITS OR OTHERWISE RESTRICTING SAID  
SERVICE WITHIN THE SEAL COVE CRITICAL GEOLTECNICAL  
HAZARDS AREA**

of private sewer pumps and laterals; excepting therefrom, repairs or replacements necessary to prevent imminent health and safety hazards. This ordinance does not revoke permits that have already been issued except that such permits or connections are subject to the imposition of service conditions necessary to protect both District owned facilities and privately owned facilities.

**SECTION 3.** This moratorium shall remain in effect for sixty (60) days, unless extended by MWSD’s Board of Directors pursuant to applicable law. During the moratorium period, MWSD will review existing geotechnical studies and conduct an infrastructure assessment to determine long-term mitigation measures and potential temporary or permanent policy updates or code amendments to be considered by the Board.

**SECTION 4.** This ordinance is exempt from the California Environmental Quality Act (CEQA) under Public Resources Code § 21080(b)(4) and CEQA Guidelines § 15269(c) (emergency actions necessary to prevent or mitigate an imminent threat to public health and safety).

**SECTION 5.** If any section of this ordinance is held invalid, the remainder shall remain in full force and effect.

**SECTION 6.** All ordinances or portions thereof in conflict herewith shall be, and hereby are, temporarily suspended to the extent of such conflict.

**SECTION 7.** Upon adoption, this ordinance shall be entered in the minutes of the Board and posted for one-week in three (3) places in the District. The Secretary of the District shall certify the passage of this ordinance and cause the same to be published once in a newspaper of general circulation published in the District.

\_\_\_\_\_  
President, Montara Water and Sanitary District

COUNTERSIGNED:

\_\_\_\_\_  
Secretary, Montara Water and Sanitary District

**ORDINANCE NO. \_\_\_\_**

**INTERIM URGENCY ORDINANCE OF THE BOARD OF DIRECTORS  
OF THE MONTARA WATER AND SANITARY DISTRICT  
TEMPORARILY SUSPENDING THE ISSUANCE OF WATER AND  
SEWER SERVICE PERMITS OR OTHERWISE RESTRICTING SAID  
SERVICE WITHIN THE SEAL COVE CRITICAL GEOLTECNICAL  
HAZARDS AREA**

\* \* \*

I HEREBY CERTIFY that the foregoing Ordinance No. 199 was duly and regularly adopted and passed by the Board of the Montara Water and Sanitary District, San Mateo County, California, at a special meeting thereof held on the 27th day of March 2025 by the following vote:

AYES, Directors:

NOES, Directors:

ABSENT, Directors:

---

Secretary, Montara Water and Sanitary District




# Geologic Analysis of the Seal Cove Area

## EXHIBIT A

### GEOTECHNICAL HAZARDS MAP SEAL COVE STUDY AREA

PLATE NO. 1 SCALE: 1"=200' DATE: 8/5/80  
 PROJECT NO. G 112-80 GEO./ENG. BY: W.C. APPROVED BY: WRC


#### GEOTECHNICAL HAZARDS MAP



#### EXPLANATION

GEOTECHNICAL HAZARD ZONE	RISK ASSESSMENT	REQUIRED GEOTECHNICAL INVESTIGATION
<b>ZONE 1</b> ■ Includes all lands located along the western seaciff that are adversely affected by active landslide processes and accelerated seaciff erosion. The position of the eastern boundary of this zone is established by the easternmost extent of active landsliding plus a setback of 50 feet. The setback zone includes lands which lie outside or east of the active landslides but are expected to experience problems in the future (i.e. 502 years).	<b>UNSTABLE</b> ■ Risk to development in this zone is considered to be extremely high. It is reasonable to conclude that slow progressive landsliding and seaciff retreat will continue, resulting in structural and property damage. This is especially true for structures or utilities located astride active surface breaks. Rapid catastrophic slope failure of the high, steep portion of the seaciff located west of Ocean Boulevard is a clear probability. Such an event could involve the loss of life as well as significant property damage. The feasibility of reducing the risk to acceptable levels is extremely low. * No additional development should be allowed in this zone.	■ No investigation deemed feasible due to the severity of the instability.
<b>ZONE 2</b> ■ Includes all lands within a 100-foot wide zone located immediately adjacent to the zone of active landsliding and accelerated seaciff erosion (i.e. Zone 1). The position of the eastern boundary of this zone is established in part by an approximate 2:1 (i.e. 261 degrees) projection measured from the base of the high seaciff located west of Ocean Boulevard.	<b>QUESTIONABLE STABILITY</b> ■ Risk to development in this zone is considered to be moderate to high. Eastward progression of active landsliding is difficult to predict with reliable accuracy. The likelihood of eliminating the risk is very low, however it may be possible to significantly reduce the impact of the hazard by properly designed foundations. * No development should be allowed in this zone until stability is clearly demonstrated by the required geotechnical investigations.	■ Engineering geologic investigation by a certified engineering geologist and a soil and foundation engineering investigation by a registered civil engineer, or a combined equivalent of the above. * Scope of both investigations should be directed toward a detailed evaluation of the potential landslide hazards in this zone. In most cases, landslide studies will require extensive subsurface work in order to provide the necessary technical data to conduct a detailed slope stability analysis. The geotechnical analysis should provide acceptable factors of safety to clearly demonstrate stability before construction is allowed in this zone.
<b>ZONE 3</b> ■ Includes all lands located outside of the areas affected by active or potential landslides.	<b>MOST STABLE</b> ■ Risk to development in this zone is considered to be low to moderate. The major geologic hazard in this zone is the threat of surface faulting along the master fault trace and several branching fault traces of the Seal Cove fault. These faults are active and capable of producing damaging surface faulting, strong ground shaking and ground failure. The relative risk associated with poor surface drainage and potentially expansive soils is generally regarded as moderate to locally high. The feasibility of reducing the risks to acceptable levels in this zone is considered high. This can be accomplished by careful siting of homes away from active faults, using careful structural and foundation design and adequate surface drainage plans. However, it is possible that some residential parcels will be judged unbuildable due to high seismic hazards. * Development should be allowed in this zone on parcels found to be free of hazardous conditions by the required geotechnical investigations.	■ Engineering geologic investigation by a certified engineering geologist and a soil and foundation engineering investigation by a registered civil engineer, or a combined equivalent of the above, unless evidence is available to show that such investigations are not required. * Scope of engineering geologic investigation should address the seismic hazards related to the master and branching traces of the Seal Cove fault. Particular emphasis of the engineering geologic investigations should be placed on the evaluation of possible surface faulting. Investigative techniques within this area will require the use of subsurface trenching and possibly geophysical traverses unless clear evidence is established to show that no active fault crosses the parcel in question. * The soil and foundation engineering investigation should address, but not necessarily be confined to, the following items: site preparation and grading, surface drainage, and design parameters for residential foundations.

#### MAP SYMBOLS



#### NOTES TO USERS

■ This map provides geotechnical data based on detailed surface mapping, interpretation of aerial photographs and the geologic data presented in the report entitled *Geologic Report of Seal Cove - Moss Beach Area*, October 15, 1971 by F. Beach Leighton and Associates. The map is primarily designed for use by geologists, engineers and planners and is not intended to be a substitute for detailed site specific geotechnical investigations.  
 Additional description and explanation of the geologic conditions of the Seal Cove study area may be found in the accompanying report entitled *Geologic Analysis of the Seal Cove Area, County of San Mateo*, August 5, 1980 by William Cotton and Associates.



GEOLOGIC ANALYSIS  
OF THE  
SEAL COVE AREA  
COUNTY OF SAN MATEO

100-100-100  
100-100-100  
100-100-100





William Cotton  
and Associates

GEOTECHNICAL CONSULTANTS

314 Tait Avenue, Lbs Gatos, California 95030  
(408) 354-5542

David C. Hale, Director  
Planning Department  
County of San Mateo  
590 Hamilton Street  
Redwood City, California 94063

August 5, 1980  
G112-80

Dear Mr. Hale:

In accordance with our agreement with the County of San Mateo (#5500-80-426) dated July 14, 1980, the final geologic report is hereby submitted.

As a result of our work, the original Geologic Map of the Seal Cove area has been updated and a number of recommendations are presented herein in order to help strengthen the present land use policies that control development.

Our report is presented in two basic parts consisting of a Conclusions and Recommendations section followed by a Technical Report section. The technical report describes the geologic data and analysis that we used to support the final conclusions and recommendations.

It has been our pleasure to be of service to the County on this interesting project. If we can be of help in clarifying any aspect of this report, please do not hesitate to contact our office.

Sincerely yours,

WILLIAM COTTON AND ASSOCIATES

William R. Cotton  
Engineering Geologist, CEG 882

bp

Attached report



CONCLUSIONS  
AND  
RECOMMENDATIONS

GEOLOGIC  
ANALYSIS  
OF THE  
SEAL COVE AREA

COUNTY OF SAN MATEO  
CALIFORNIA

August 1980





## CONCLUSIONS

The Seal Cove study area is exposed to a variety of geologic hazards that severely affect future land use decisions. These conditions and the level of associated risk were well documented nearly a decade ago by a County-authorized geologic study conducted by Leighton and Associates (October 1971). The present study was designed to update the geologic information presented in the Leighton report and to reevaluate the residential development regulations.

The following geologic hazards are the principal geologic concerns of the Seal Cove area:

Landsliding - Deep-seated landslides presently are destroying extensive sections of the seacliff region which define the western edge of the study area. Approximately 17 homes have suffered some form of structural damage due to landslide activity. The inland extent of the active landsliding from the coastline ranges between 100 to 400 feet; however, the average distance is nearly 250 feet. The average rate of landslide movement is very slow, probably ranging between 1 and 3 inches per year. However, the probability of accelerated movements is considered high in many local areas within the presently failing landslide complex. This is especially true of the high seacliff area located west of Ocean Boulevard where rapid catastrophic failure is a clear possibility.

Faulting - The active Seal Cove fault and a number of branching fault traces pass through the study area. The main trace is confined to a 100-foot-wide zone located along the eastern margin of the study area. Although most of this zone lies outside of the study area, the branching fault traces pass through the main portion of the residential area. All of these faults are considered to be active, and thus, capable of generating earthquakes with associated ground shaking, surface faulting and ground failure.

Seacliff Erosion - The entire coastline area presently is experiencing severe erosion by wave activity. This erosion process causes the seacliff to become undercut at its base and locally unstable. The oversteepened face of the seacliff responds by shallow, piecemeal sloughing; however, natural stability is never achieved due to the constant erosional activity within the surf zone. The result is a systematic retreat of the seacliff by local episodic sloughing. The average rate of cliff retreat is approximately 3 to 4 feet per year in the Seal Cove area.

A number of additional geologic problems have been identified in the Seal Cove area; however, these are

relatively minor hazards when compared to those outlined above and can be significantly mitigated by design. These problems include potentially expansive soils, poor surface drainage and problems associated with shallow ground water.

### RISK ANALYSIS

The development of sound public policy to deal with the geologic hazards of the Seal Cove area requires an answer to the question, "How safe is safe enough?" The information and analysis presented in this report is an attempt to provide the necessary framework on which the appropriate County decisionmakers can judge acceptable levels of risk.

To properly assess the appropriate level of risk to the community, a number of important steps are essential. First, and probably most importantly, the presence of geologic hazards must be recognized. In the Seal Cove area, although the original subdivision was initiated in the early 1900's, the hazardous landslide and fault conditions were not recognized until nearly ten years ago. Consequently, many homes and streets were built on active landslides or astride active traces of the Seal Cove fault, and thus, have sustained considerable damage.

The second step in this process takes place after the geologic hazards have been recognized. This step requires detailed studies to determine the physical characteristics of the hazards. For the Seal Cove area, this was accomplished through the initial geologic study conducted by Leighton and Associates in 1971. They identified a large area of active landslides, and a number of fault traces associated with the Seal Cove fault. As an important part of their investigation, they provided a detailed description of the dimensions and level of activity of the landslides and faults.

Once the geologic hazards are recognized and carefully characterized, then the degree or level of risk associated with each hazard can be evaluated. In the Seal Cove area the present land use tends to limit the exposure of risk mainly to utilities, streets and houses; however, the potential for personal injury or loss of life is possible in local areas. The decision as to whether the various levels of risk are tolerable or intolerable to the public requires the input of the County decisionmakers. An important part of any risk analysis is the consideration of possible mitigating measures that could reduce the risk associated with each type of hazard. This kind of action is usually the product of the democratic process and depends as much on social, economic and environmental values as on geologic knowledge. There are a number of mitigating measures that may reduce risk to tolerable levels. For example, land use may be regulated to the degree that residential development is simply restricted from

hazardous areas, thus the hazard is avoided and the risk is essentially eliminated. This has been done in the Seal Cove area by prohibiting construction in active landslide areas, astride active fault traces and close to the edge of the seacliff.

Another method of reducing the risk is by attempting to reduce the impact of the hazard. This might include requirements for special foundations for residential structures, improved drainage facilities, flexible utilities and stronger construction techniques. No significant attempts have been made in the Seal Cove area to reduce the impact of landslide or fault hazards by design, and indeed, to attempt to do so does not seem reasonable. Likewise, attempts to reduce the risk associated with the landslides and faults by controlling these hazardous processes is impractical, if not impossible.

In summary, it is our opinion that the only practical means of reducing the risk associated with landslide and fault hazards is by prudent land use regulations. Any land use policy should balance the risk against the social, economic and environmental cost in order to determine the level of risk acceptable to the community.

#### RECOMMENDATIONS

The following recommendations are presented for consideration by the County in order to establish prudent land use policies within the Seal Cove area. We believe that the recommendations are consistent with the goals and objectives of the Seismic Safety Element of the General Plan, the original recommendations presented in the Leighton report, and the minimum standards for geotechnical reports which were adopted by the County in 1977. However, after careful review by the County these recommendations may be altered to reflect the final expression of the County perception of acceptable risk.

1) Critical Hazards Area - Due to the complexity of the hazardous geologic conditions in the Seal Cove area we recommend that the entire study area be designated as a "Critical Geotechnical Hazards Area." Such a designation would "red flag" the region as an area of high geologic hazards for which special or more detailed geologic and soil investigations (i.e. geotechnical) will be required prior to development. Additionally, such a designation would alert present and future landowners to the hazardous conditions and the potential higher than normal cost of development.

To protect the interest of the County, individual landowners, and local developers geologic and/or soil investigations of appropriate level should be required for all lands within the study area. These investigations will normally exceed the minimum standards adopted by the County and will specifically address the primary geology and hazard of the site in question.

2) Geotechnical Hazards Map - To facilitate the required geologic and/or soil investigations we have prepared a new hazard zonation map for the Seal Cove area. This map is a modification of the original map prepared by Leighton and Associates in 1971 and is based upon new landslide and fault information generated during the present study. The changes from the original zonation map include (1) combining hazard zone 3 and 4, and (2) moving the boundary of hazard zone 1 and 2 to the east. The geotechnical hazard zones have been compiled on the new 200-scale County base map which we believe is a more useful map because it superimposes property boundaries on an orthophotographic base.

The Geotechnical Hazards Map divides the Seal Cove area into three zones on the basis of similar geotechnical hazards or problems. Consequently, the terrain within each zone is considered to have similar potentials and constraints for development. In essence each zone reflects different levels of risk to man and structures.

The physical conditions and the associated risk of the three zones are described on the Geotechnical Hazards Map along with the various levels of geotechnical investigations required to evaluate the particular hazards in each zone. The following section describes the criteria for each hazard zone, defines the associated risk for development in each zone and defines the scope of required geotechnical investigations. It is recommended that the Geotechnical Hazards Map be officially adopted by the County as part of the final land use policy to guide future development in the Seal Cove study area.

**ZONE 1** - Includes all lands located along the western seacliff that are affected by active landslide processes and accelerated seacliff erosion. The position of the erosion boundary of this zone is established by the easternmost extent of active landsliding plus a setback of 50 feet. The setback zone includes lands which lie outside or east of the active landslides but are expected to experience problems in the future (i.e. 50± years).

Risk Assessment - Risk to development in this zone is considered to be extremely high. It is reasonable to conclude that slow progressive landsliding and seacliff retreat will continue, resulting in structural and property damage. This is especially true for structures or utilities located astride active surface breaks. Rapid catastrophic slope failure of the high, steep portion of the seacliff located west of Ocean Boulevard is a clear probability. Such an event could involve the loss of life as well as significant property damage.

The feasibility of reducing the risk to acceptable levels is extremely low.

No additional development should be allowed in this zone.

**ZONE 2** - Includes all lands within a 100-foot wide zone located immediately adjacent to the zone of active landsliding and accelerated seacliff erosion (i.e. Zone 1). The position of the eastern boundary of this zone is established by a 2:1 (i.e. 26½ degrees) projection measured from the base of the high seacliff located west of Ocean Boulevard.

Risk Assessment - Risk to development in this zone is considered to be moderate to high. Eastward progression of active landsliding is difficult to predict with reliable accuracy.

The likelihood of eliminating the risk is very low, however it may be possible to significantly reduce the impact of the hazard by properly designed foundations.

No development should be allowed in this zone until stability is clearly demonstrated by the required geotechnical investigations.

Required Geotechnical Investigation - Engineering geologic investigation by a certified engineering geologist and a soil and foundation engineering investigation by a registered civil engineer, or a combined equivalent of the above.

- Scope of both investigations should be directed toward a detailed evaluation of the potential landslide hazards in this zone. In most cases, landslide studies will require extensive subsurface work in order to provide the necessary technical data to conduct a detailed slope stability analysis. The geotechnical analysis should provide acceptable factors of safety to clearly demonstrate stability before construction is allowed in this zone.

**ZONE 3** - Includes all lands located outside of the areas affected by active or potential landslides.

Risk Assessment - Risk to development in this zone is considered to be low to moderate. The major geologic hazard in this zone is the threat of surface faulting along the master fault trace and several branching fault traces of the Seal Cove fault. These faults are active and capable of producing damaging surface faulting, strong ground shaking and ground failure.

The relative risk associated with poor surface drainage and potentially expansive soils is generally regarded as moderate to locally high.

The feasibility of reducing the risks to acceptable levels in this zone is considered high. This can be accomplished by careful siting of homes away from active faults, using careful structural and foundation design and adequate surface drainage plans. However, it is possible that some residential parcels will be judged unbuildable due to high seismic hazards.

Development should be allowed in this zone on parcels found to be free of hazardous conditions by the required geotechnical investigations.

Required Geotechnical Investigation - Engineering geologic investigation by a certified engineering geologist and a soil and foundation engineering investigation by a registered civil engineer, or a combined equivalent of the above.

- Scope of engineering geologic investigation should address the seismic hazards related to the master and branching traces of the Seal Cove fault. Particular emphasis of the engineering geologic investigations should be placed on the evaluation of possible surface faulting. Investigative techniques within this area will require the use of subsurface trenching and possibly geophysical traverses unless clear evidence is established to show that no active fault crosses the parcel in question.
- The soil and foundation engineering investigation should address, but not necessarily be confined to, the following items: site preparation and grading, surface drainage, and design parameters for residential foundations.

All of the geotechnical investigations should reference this report and the geologic data presented in the Leighton and Associates report of 1971 and the Seismic and Safety Elements of the General Plan of 1976. The geotechnical reports describing the results of these investigations should be reviewed by the County Geologist following the procedure that is currently in practice. The recommendations expressed in the soil and foundation engineering reports and/or the engineering geologic reports should become conditions of any development application.

TECHNICAL REPORT

GEOLOGIC ANALYSIS  
OF THE  
SEAL COVE AREA

County of San Mateo  
California

August 1980







William Cotton  
and Associates

GEOTECHNICAL CONSULTANTS

314 Tait Avenue, Los Gatos, California 95030  
(408) 354-5542

To: David C. Hale  
Planning Director  
County of San Mateo  
August 5, 1980  
Project G112-80

From: William Cotton and Associates  
Geotechnical Consultants

Subject: Geologic Analysis  
Seal Cove Area  
County of San Mateo, California

INTRODUCTION

At the request of the County of San Mateo we have completed an investigation of the geologic conditions of the Seal Cove area. The primary purpose of our work was to evaluate and update the existing Geologic Map of the area, to identify and characterize the geologic hazards that constrain development, and to evaluate the level of risk associated with the hazardous conditions.

The geologic investigation included the following tasks: (1) detailed geologic surface mapping of the study area at a scale of 1 inch = 200 feet, (2) compilation and analysis of geologic and soil engineering data taken from reports and maps held in the County files, (3) stereoscopic evaluation of sequential aerial photographs, and (4) discussions with area landowners. The equivalent of eight man-days were spent collecting and compiling field data.

In preparing this report we have relied heavily on the following documents:

- Geologic Report of Seal Cove and Moss Beach Area,  
F. Beach Leighton and Associates,  
October 15, 1971.
- Geotechnical Hazards Synthesis Map for  
San Mateo County, Leighton and Associates,  
and San Mateo County Planning Department,  
June 1975.
- Seismic and Safety Elements of the  
General Plan, Vol. 1 and 2; San Mateo  
County Planning Department, December 1976.

The geologic data and discussions presented in this report should be regarded as updated and reevaluated information taken from the Leighton report and should not be considered to supersede or diminish the importance of their work. Future development in the Seal Cove area should not proceed without reference to both of these reports and the data compiled for the seismic safety element of the County of San Mateo.

#### ACCOMPANYING ILLUSTRATIONS

Geotechnical Hazards Map, 1 inch = 200 feet, Plate 1 Pocket

Index Map, Figure 1

Topographic and Geologic Index Map, Figure 2

Schematic Geologic Cross Section, Figure 3

Mode of Rock Slump Failure, Figure 4

Progressive North to South Failure of Seacliff Region, Figure 5

Progressive Seacliff Erosion, Figure 6

Seal Cove Fault System, Figure 7

## DEVELOPMENT HISTORY

The portion of coastal San Mateo County that is included in this study is a residential section known as Seal Cove which is located in the southern part of the community of Moss Beach (Figure 1). The northern and southern boundaries of the study area are defined by Cypress and Bernal Avenues, respectively, and include all of the residential property located between the Half Moon Bay Airport and the ocean.

The Seal Cove area was subdivided into residential parcels about 1908. The area was subdivided into 2500 square foot lots with roads and improvements (i.e., streets, sidewalks and utilities) without regard for the geologic constraints. In fact, the primary attraction of the Seal Cove area was the presumed relatively low level of risk associated with the setting as compared to the San Francisco region that was devastated during the earthquake of 1906. The existing street alignments and the lot configurations are essentially the same as the original 1908 development plan. Since that time, residential construction has proceeded at a rather slow, piecemeal rate with home construction being limited to parcels of 5000 square feet.

In the late 1960's development in portions of the Seal Cove community was identified by the U.S. Geological Survey as being constrained by high geologic hazards due to active landsliding and accelerated coastal erosion. On the basis of this information, the County of San Mateo placed a building freeze on the Seal Cove area and authorized Leighton and Associates, the County Geologists, to complete a detailed geologic study of the area and to provide the County with guidelines for future development. The geologic study was completed and the final report was accepted by the County in October of 1971. The Leighton report clearly identified the primary geologic constraints of the Seal Cove as landsliding, faulting, and seacliff erosion. In addition, the report identified less severe potential problems associated with poor surface drainage, high ground water, and expansive soils. On the basis of these concerns, the Seal Cove area was divided into four Geologic Hazard Zones that define different levels of relative geologic stability. The description of each zone identifies the primary geologic hazard that constrains development and defined the type of geologic and soil report that would be required prior to residential development. Table 1 outlines the four hazard zones as presented in the Leighton report of October 15, 1971.




FIGURE 1 - INDEX MAP  
 SEAL COVE STUDY AREA  
 COUNTY OF SAN MATEO, CALIFORNIA

ZONAL RATINGS	GEOLOGIC STABILITY RATINGS	MAJOR GEOLOGIC PROBLEM TYPES	NATURE OF FUTURE GEOLOGY AND SOILS REPORTS REQUIRED
1	MOST SEVERE INSTABILITY	LANDSLIDING (RAPID MOVEMENTS LIKELY)	FEASIBILITY OF CORRECTION HIGHLY IMPROBABLE
2	UNSTABLE	PROGRESSIVE LANDSLIDING, EROSIONAL RETREAT OF BLUFFS, HIGH GROUND WATER AND ACTIVE FAULTING	DETAILED SUBSURFACE INVESTIGATIONS WILL BE NECESSARY TO ANALYZE INSTABILITY
3	DEGREE OF INSTABILITY QUESTIONABLE	COMBINATIONS OF THE ABOVE	DETAILED SUBSURFACE INVESTIGATIONS WILL BE NECESSARY TO DETERMINE DEGREE OF STABILITY
4	MOST STABLE	TYPICAL SOILS PROBLEMS (EXPANSIVE SOILS, ETC.); LOCALIZED GEOLOGIC PROBLEMS (SOIL CREEP, ETC.); SEISMIC RESPONSE, ETC.	CONVENTIONAL INVESTIGATIONS WILL PROBABLY BE ADEQUATE

TABLE 1 - GEOLOGIC HAZARD ZONES AS DEFINED BY LEIGHTON AND ASSOCIATES, OCTOBER 15, 1971

In November of 1971 the County accepted the conclusions and recommendations of the Leighton report and imposed a number of building restrictions on the parcels within the four hazard zones. In addition, Leighton and Associates prepared and sent to the County a specified set of guidelines for geologic and soil investigations conducted in the Seal Cove area. On the basis of the new information, the building freeze was lifted but residential development was allowed to proceed only after the necessary geologic and/or soil investigations were satisfactorily completed. The required reports were reviewed by Leighton and Associates on a part-time basis until 1975 when the County retained A. C. Neufeld as the permanent County Geologist.

The present policy regarding geologic and soil reports has been altered slightly from the recommendations of the Leighton report. At present, detailed geologic and soil investigations are required in Geologic Hazard Zones 1 and 2; however, in zones 3 and 4 such investigations are only required when a parcel is located within fifty feet of a mapped fault. Normally, areas located outside of the fifty foot zone do not require any geologic or soil report prior to construction. The adequacy of the geologic and soil report are evaluated by the County Geologist according to the Minimum Standards for Geotechnical Reports adopted by the County and the review procedures developed by the County Geologist. In some cases the County Geologist has imposed stricter and, at times, more reduced standards where local geology or soil data warrant such changes.

Since the suspension of the 1971 building freeze, 16 new homes have been constructed in the study area. These homes are situated within the following Geologic Hazard Zones as defined by Leighton and Associates:

ZONE 1 - Most severe instability	- no development
ZONE 2 - Unstable	- 9 new homes
ZONE 3 - Degree of instability questionable	- 5 new homes
ZONE 4 - Most stable	- 2 new homes

Our evaluation of the locations and conditions of the new homes indicates that the present stability of most homes is good; however, the safety of two of these homes is in question. These homes are situated in Geologic Hazard Zone 2. The specific locations and geologic concerns of these structures are outlined below:

LOCATION

GEOLOGIC PROBLEM

131 La Grande Avenue

Home, deck and patio constructed within several feet of an active landslide scarp

821 Ocean Boulevard

Front portion of home and driveways are situated over an active landslide tension crack

The home on La Grande was constructed east of a major, active landslide scarp that was well documented in the Leighton report, and recognized by the owner's consultants prior to construction. But at the time that the home on Ocean Boulevard was constructed, no surface evidence of landsliding was noted. Apparently the landslide-related surface cracking has extended to this location since the Leighton investigation of 1971. Small incipient surface cracks can be traced from the parcel on Ocean Boulevard to the east under the neighboring parcel where residential damage is more pronounced, and then north across La Grande Avenue to the prominent scarp area located west of 131 La Grande Avenue.

Our analysis of the geologic hazards of the Seal Cove area indicate that the landslide activity is progressing as predicted nearly a decade ago; however, the previously mapped fault pattern appears to be more complex. As a result of our work we have reevaluated the original hazard zones and have altered the positions of some boundaries. Additionally, we have recommended specific changes in the type and scope of future geotechnical investigation in the Seal Cove area.





PHYSICAL PARAMETERS: Topographic, Geologic and Seismic

The Seal Cove area is characterized by a unique set of physical parameters that strongly influence safe development. The physical conditions that have the most influence are those that relate to the topographic, geologic and seismic setting of the study area. The general characteristics of each of the conditions and their associated constraints and potentials for development are described in the following sections.

TOPOGRAPHIC SETTING - The portion of the community of Moss Beach that is included in this investigation is situated at the north end of a prominent northwest-trending ridge (Figures 2 and 3). The ridge extends from Pillar Point on the south to beyond Seal Cove for a distance of approximately two miles. An east-west profile across the ridge is asymmetrical, characterized by a high, near-vertical seacliff along the western side, a nearly flat terrace surface along the top of the ridge, and a gentle, east-facing slope along the eastern border. The average elevation is nearly 100 feet throughout most of the ridge area, but the ridge top rises to approximately 175 feet above sea level south of the study area. Within the immediate residential portion of the study area the topography is relatively flat with a topographic relief of no more than 25 feet.

The present topography of the Seal Cove area and the surrounding ridge is the product of a long history of rather dynamic geologic processes, of which most are still actively modifying the area. These processes include active landsliding, accelerated seacliff erosion and young fault activity. The terrain that is not affected by these hazardous processes have a relatively high potential for safe development. Such areas are within the essentially flat terrace region situated east of Beach Way and Ocean Boulevard.

GEOLOGIC SETTING - The geologic setting of the Seal Cove area is defined by a variety of earth materials, active slope failure processes and a complex fault zone related to the Seal Cove fault system. The following discussion is designed to present a general description of the geologic setting. For a more detailed account, the Geologic Report of Seal Cove-Moss Beach Area, October 15, 1971 by F. Beach Leighton and Associates, should be consulted. Their report presents a large volume of detailed surface and subsurface geologic data in written and illustrative form. The description of the geologic setting included in this report is based on our field mapping and the information presented in the Leighton report.

The primary earth materials in this part of the Seal Cove community can be divided into two dramatically different types of bedrock units which are overlain by two types of

# EXPLANATION

## Earth Materials

## Map Symbols

### SURFICIAL UNITS

**Qls - Landslides**

Rock slumps of surficial  
and bedrock material

**Qt - Marine Terrace**

Unconsolidated gravel,  
sand and silt


### BEDROCK UNITS

**Tp - Purisima formation**


Highly fractured siltstone,  
shale and sandstone

**Kg - Montara Quartz Diorite**

Coarse-grained quartz  
diorite

 Geologic Contact

 Faults

 Landslides




FIGURE 2. TOPOGRAPHIC AND GEOLOGIC INDEX MAP

SEAL COVE STUDY AREA  
 COUNTY OF SAN MATEO, CALIFORNIA  
 Scale 1 inch = 2,000 feet

Topographic base map, Montara Mountain and Half Moon Bay Quad-  
 rangles, 7.5 minute. U.S. Geological Survey




FIGURE 3 SCHEMATIC GEOLOGIC CROSS SECTION

SEAL COVE STUDY AREA  
 COUNTY OF SAN MATEO, CALIFORNIA

surficial deposits (Figures 2 and 3). The two bedrock units consist of a relatively fine-grained sequence of sedimentary rocks belonging to the Purisima formation (Tp) and a massive coarse-grained igneous rock of the Montara Quartz Diorite (Kg). These materials make up the bulk of the rock materials that form the prominent ridge topography, however, in most areas the bedrock is covered by the surficial deposits. The surficial materials consist of a sedimentary Marine Terrace deposit (Qt) that blankets all of the nearly flat topography of the study area, and a complex of active landslides deposits (Qls) which are presently destroying large sections of the western seacliff region. The following discussion describes the physical nature of each type of earth material in the Seal Cove area.

Surficial Units - the relatively unconsolidated deposits that overlie the bedrock material.

Landslide (Qls) - The landslide deposits are composed of both the overlying surficial Marine Terrace and the Purisima bedrock materials. The primary type of failure appears to be rock slump with movement concentrated along deep-seated failure planes. The landslides are concentrated in a coastal belt along the western margin of the study area that extends inland as far as 300 to 400 feet.

Marine Terrace (Qt) - These deposits form a blanket-like covering of gravel, sand, and silt that overlies the bedrock units throughout the relatively flat portion of the study area. The thickness ranges from 3 to 4 feet to as much as 40+ feet.

Bedrock Units - the relatively consolidated materials which form the major portion of the ridge and which the surficial units rest.

Purisima formation (Tp) - This unit consists of a thin-bedded, highly fractured, inter-layered sequence of siltstone, shale, and sandstone. The bedrock is exposed along the entire length of the seacliff area and has been encountered in drill holes located approximately 800 feet east of the seacliff area.

Montara Quartz Diorite (Kg) - This bedrock type is not exposed at the surface but has been penetrated in drill holes along the eastern margin of the study area. It consists of deeply-weathered, medium- to coarse-grained quartz diorite.

The most active geologic process now operating in the study area are two distinctly different types of slope failure. They are confined to the seacliff region and include (1) deep-seated landsliding involving large segments of the seacliff, and (2) shallow sloughing and ravelling of the face of the seacliff.

LANDSLIDING - Active, deep-seated landsliding presently is affecting most of the seacliff located along the western margin of the study area. The average height of the seacliff is approximately 100 feet and, in most cases, the entire seacliff is involved in landsliding. The locations of the crowns (i.e. tops) of the landslides vary considerably, but in several places the crowns are located as much as 300 to 400 feet back (i.e. east) of the top of the seacliff, however, the average distance is nearly 250 feet. The depth to the basal slide planes of these landslides is not well known, but from the surface dimensions it is estimated that the depths equal or exceed the height of the seacliff. Thus, the toes (i.e. bottoms) of most of these landslides are near the base of the seacliff and sea level (Figure 4).

Detailed surface mapping and subsurface drill hole data strongly suggest that the mode or style of slope failure can be characterized as (1) progressing from the north to the south and (2) undergoing rotational failure along a concave-upward basal rupture surface. The north-to-south progressive failure is revealed by the pattern and dimension of the surface breaks noted along the crowns of the individual landslides (Figure 5). For example, the eastern limits of the landslides are commonly defined by one or more landslide-related geomorphic features including prominent crown scarps, trenches (i.e. grabens), linear depressions and tension cracks. The pattern of failure normally starts with a well-developed headwall scarp near the crown of a major landslide block. The scarps commonly are more prominent and better developed along their northern extensions. Most can be traced to the south along somewhat discontinuous curvilinear paths, but the scarps frequently diminishes in height to the south and eventually are replaced by shallow linear depressions or a series of tension cracks. Consequently, it appears that most of the landslide headwall scarps propagate slowly to the south from their points of initiation, following a scissor-like pattern with greater surface displacements being concentrated along the northern extension of the headwall scarps.

Although the basal rupture surfaces for most of the landslides is not well defined, they appear to be controlled structurally by the orientation and the spacing of the bedrock fractures. The stratification of the bedrock is inclined into the seacliff. Such an orientation usually accounts for increased slope stability, but the highly fractured nature of the bedrock and the presence of a prominent set of west-dipping continuous fractures reduce the strength of the bedrock and controls the mode of failure.




FIGURE 4 MODE OF ROCK SUMP FAILURE  
SCHEMATIC CROSS SECTION

SEAL COVE STUDY AREA  
COUNTY OF SAN MATEO, CALIFORNIA






FIGURE 5 PROGRESSIVE NORTH TO SOUTH  
FAILURE OF SEA CLIFF REGION

SEAL COVE STUDY AREA  
COUNTY OF SAN MATEO, CALIFORNIA


Thus when the relatively incompetent bedrock is exposed in a high, near-vertical seacliff that has been oversteepened by wave erosion, the rock becomes detached along the planar surfaces of the fractures. Consequently the seacliff fails in a type of landslide known as a rock slump (Varnes 1978) which normally involves bedrock materials that fail by rotation along a curved basal rupture surface.

The rate at which these large deep-seated landslide masses are failing can be estimated roughly by noting the increase in the scarp heights and in the length of extensions of the tension cracks since the completion of the original landslide mapping in 1971 (i.e. Leighton and Associates). Our measurements indicate that the rate of failure probably is approximately 1 to 3 inches per year; thus the rate of movement is regarded as very slow. However, the possibility of accelerated movements is considered high in many local areas within the presently failing landslide complex.


SLOUGHING - The most active form of slope failure along the seacliff is shallow, small-scale sloughing and ravelling of the face of the cliff. This process is initiated by wave erosion concentrated along the base of the seacliff (Figure 6). This erosional process causes the base of the seacliff to become undercut and locally unstable. The face of the seacliff responds to the oversteepened condition by localized piecemeal sloughing and ravelling. Most of the cliff retreat takes place during the winter season when storm waves vigorously erode and undercut the base of the seacliff. The weak, highly fractured siltstone and shale bedrock and the unconsolidated cover of marine terrace material are left in an oversteepened and unsupported condition, and consequently fail. The fallen debris temporarily protects the base of the cliff, but the waves eventually remove the debris and the oversteepening process starts anew.

An analysis of aerial and ground photographs taken over a period of fifty years, 1926 to 1976, and map extending back approximately 130 years reveals that the average rate of cliff retreat within the study area is now approximately 3 to 4 feet per year. However, this process is episodic and is controlled by a variety of local geologic conditions, thus the average rate cannot be projected into the future with any degree of certainty. For example, using this rate, it would be unreasonable to predict that the top of the seacliff will be located 30 to 40 feet east of its present location by 1990; there may be only 5 feet of cliff retreat in the next ten years, but 55 feet of retreat may occur the subsequent decade. Thus the average rate over a 20 year period would approximate 3 feet per year.


In conclusion, the seacliff portion of the Seal Cove area presently is failing by large deep-seated landsliding and small scale localized sloughing. Although both of these types of failures are partially induced by the oversteepening process



**Stage 1 - Relatively Stable Seacliff**



**Stage 2 - Local instability due to undercutting of base of seacliff**



**Stage 3 - Relative stability attained by piecemeal sloughing and ravelling**

**FIGURE 6 PROGRESSIVE SEA CLIFF EROSION  
SCHEMATIC DRAWINGS**

SEAL COVE STUDY AREA  
COUNTY OF SAN MATEO, CALIFORNIA

of wave erosion, they are dramatically different in scale and mode of failure. Likewise each presents a very different level of risk to future development.

In our judgment, attempts to control or reduce these hazards by engineering design would not be feasible. The scale of the large active landslides make any stabilization scheme essentially uneconomical, likewise an engineering solution needed to stop the erosional activity at the base of the seacliff would severely impact the James V. Fitzgerald Marine Reserve which includes the Seal Cove surface zone. Consequently it appears the most prudent way to reduce the risk is to avoid the areas that are vulnerable to these slope failure hazards.

SEISMIC SETTING - The principal structural feature within the study area is the Seal Cove fault zone and a number of subsidiary branch faults (Figure 7). The master trace of the fault appears to lie near the base of the east-facing slope which forms the eastern boundary of the study area. Here the master trace is considered to be within a zone of pulverized rock that is approximately 100 feet wide. West of this main zone, the location and character of faulting are less well understood. In this region at least three branch faults extend to the southeast from the main Seal Cove fault zone and pass through the study area (Leighton 1971). Subsequent site-specific geologic studies have confirmed with slight modifications the location of some of these branch fault traces. In addition, the analysis of aerial photographs conducted for this study and by A. C. Neufeld, San Mateo County Geologist, strongly indicate that several additional fault-related lineations cross the relatively undeveloped area located south of San Lucas Avenue.

These branch faults, like those in the main fault zone are considered to be normal faults characterized primarily by vertical displacements. The main fault trace is identified as the zone of greatest concentration of displacement. Indeed the east-facing slope that forms the eastern boundary of the study area is considered to be a fault scarp produced by displacement along the main trace of the Seal Cove fault. Although the branch faults also are considered to be active traces, both the surface expressions of these faults and the subsurface data presented by the Leighton report indicate that the amount of displacement and the state of activity along these faults probably is much less than the master trace.

Recent fault studies suggest that the Seal Cove fault zone is a segment of a major coastal boundary fault zone that merges with the San Andreas fault north of San Francisco (Greene and others, 1973; Weber and Cotton, 1980). This fault zone includes the Seal Cove, San Gregorio, Sur, San Simeon and Hosgri faults and extends to the south for more than 260 miles to the vicinity of Point Arguello. The largest historic seismic event recorded along the San Gregorio fault system





FIGURE 7 SEAL COVE FAULT SYSTEM

SEAL COVE STUDY AREA  
COUNTY OF SAN MATEO, CALIFORNIA

were two Richter magnitude 6.1 earthquakes which occurred within one hour of each other near the center of Monterey Bay in 1926. Studies of historic seismicity along the San Gregorio fault zone in the vicinity of Monterey Bay indicate that the fault zone probably is capable of producing an earthquake of Richter magnitude 7.2 - 7.9. Paleoseismologic research on the San Gregorio fault zone near Point Ano Nuevo, in San Mateo County, suggests that (1) earthquakes of Richter magnitude 7.6 - 7.7, and possibly greater than Richter magnitude 8.0, have occurred along the San Gregorio fault zone in the past and are anticipated to occur in the future, and (2) a reasonable estimate of the recurrence interval for major earthquakes (M 7.5) along the San Gregorio fault system is 225-400 years and probably is about 300-325 years (Weber and Cotton, 1980). Since the Seal Cove fault is considered to be an extension of the San Gregorio fault system, it is reasonable to attribute a similar level of seismic activity to the Seal Cove area.

In conclusion, the main trace and the branching traces of the Seal Cove fault are considered to be active. The branching faults located in the relatively undeveloped area south of San Lucas Avenue are only approximately located. Indeed, there may be additional fault strands that are as yet unrecognized in this region. Should a major earthquake take place along the Seal Cove fault the anticipated seismic hazards would be severe ground shaking, surface faulting along the master trace and branching fault traces and ground failure (landsliding, sloughing, settlement, etc.). The risk associated with these hazards can be dramatically reduced by carefully siting homes away from active fault traces or potential zones of ground failure and by careful structural and foundation design.





SEAL COVE  
GEOLOGICAL HAZARDS ZONES





The Honorable Board of Supervisors  
San Mateo County  
County Government Center  
400 County Center, 1st Floor  
Redwood City, CA 94063

Re: Impacts of recent land movement in Seal Cove Critical Geotechnical Hazards Area on water and sewer service

Hon. Board of Supervisors:

I am writing on behalf of the Montara Water and Sanitary District (MWSD) to bring your attention to the urgent challenges we are facing with our sewer and water facilities in the Seal Cove area, specifically along San Lucas Road, Del Mar Avenue, and Ocean Boulevard adjacent to the coastal bluffs. These County roads and the surrounding areas are experiencing significant active land instability, including erosion, sinkholes, and soil movement, which is severely impacting our ability to provide essential services to several homes in this area. Our Board has recently taken emergency measures, including the adoption of an emergency resolution (attached) that includes the District's request that the County exercise its authority to proclaim the existence of a local emergency in the area.

A critical concern is the County's recent closure of San Lucas Road due to sinkholes that have rendered the road impassable for emergency vehicles. San Lucas Road, along with the other public roads in this area, provides the only access to several of the District's water and sewer facilities that serve local residents. The closure of this road has created a significant barrier to emergency response, limiting our ability to perform necessary repairs and maintenance on critical infrastructure.

Moreover, much of MWSD's affected infrastructure is located within the public right of way, and as such, the County holds jurisdiction over maintaining the safety, accessibility, and environmental integrity of these public roads. The County's primary responsibility in this regard is to ensure the safe, functional use of public roads and to support the infrastructure of utility providers like MWSD. However, due to the ongoing land instability, including erosion along the coastal bluffs, sinkholes, and other geological hazards, MWSD faces increasing challenges in providing safe and reliable water and sewer services. Further, the County continues to issue building permits in the area which have greatly impacted the District's ability to provide service. These conditions are not only impeding emergency access but are also presenting ongoing risks to the health and safety of our system, customers, and field staff.

After careful review, we believe that further maintenance and continued utility service in this high-risk area may no longer be feasible. We are committed to addressing the safety of the community and the environment, as well as MWSD's legal obligations to provide water and sewer services in a safe and reliable manner. However, the instability of the land and the possible consequences of maintaining infrastructure in such a hazardous area requires a detailed and coordinated assessment.

Given that MWSD is responsible for maintaining critical infrastructure that serves the community, we urgently request your assistance in addressing these issues. Specifically, we seek:

- Collaboration with the County to explore solutions that will restore access to critical facilities, particularly those along San Lucas Road and Ocean Boulevard, while addressing the ongoing geotechnical hazards.
- Input and Support for Regulatory Compliance: We would appreciate the County's expertise and assistance in understanding any regulatory hurdles or approvals that might be required to continue or discontinue service in this area, particularly regarding coastal development and the County's LCP and applicable zoning regulations.
- Geotechnical Studies and Risk Mitigation: We urge the County to update its studies supporting its land use polices; we also seek input on potential strategies for reinforcing or relocating infrastructure and whether there are county-based resources that might assist with funding or coordination.
- Assistance from the County in securing emergency funding or resources to support necessary infrastructure stabilization efforts and the repair of affected roads and utilities.
- Joint Communication with Affected Property Owners: We believe that working together with the County will strengthen our communication efforts with property owners in the affected area and help identify workable solutions for all stakeholders involved.
- A long-term strategy to address the geotechnical instability in this area, which is essential for safeguarding the public health, the environment, and ensuring service continuity for residents.

We understand that these challenges are complex and require collaboration across jurisdictions. However, the safety and well-being of our residents must be a top priority, and we ask for the County's support in mitigating the risks posed by land instability and providing the necessary resources to stabilize our facilities, which are critical to retaining residency/occupancy of private properties. We are available to meet with your team to discuss these concerns in more detail and explore possible solutions.

Thank you for your attention to this urgent matter. We look forward to working with the County to resolve these challenges and ensure continued utility service delivery in this critical area.

Sincerely,

Scott Boyd  
President, Board of Directors of the Montara Water and Sanitary District

Cc: Steve Monowitz, SMC Director of Planning and Building  
Ray Mueller, SMC Board of Supervisors, District 3